



STATE OF COLORADO Cover Sheet for Building Specifications, Third Party Reviews, and QA Manuals

Name of Manufacturer:	Champion Home Builde	rs	Plant I.D. Number: 165			
	3200 Enterprise Ave., You					
			Shaun Penne - 402-362-4455			
	mail address: CWalker@Ch					
	Third Party Inspection Agency (if not CDOH): Nebraska Public Service Comm. Housing & RV Dept					
Third Party Plan Review Agency (if applicable): PFS TECO						
Third Party Plan Review Approval Name/Number (if applicable): PFS 500206OC						
Factory Type: xxFB	FBNR Tin	y Homes	HUD Homes			
Document Type:XX New	Plan Revision Rer	newal				
Model Name/No.: 05-865-HERBERT						

MANUFACTURER CERTIFIES that only approved equipment and materials will be used and the installations shall be made in accordance with approved plans and applicable codes and provisions of the Colorado Division of Housing. Manufacturer agrees to in-plant inspection of units manufactured under the above plan approval. Application shall be made for and insignia affixed to each factory built unit that is subject to Colorado statutes and which is manufactured or is to be sold, offered for sale, or occupied in the state of Colorado.

Sq. Footage Finished: 1865	
Sq. Footage Unfinished:	
CDOH Approval Stamp	
Expiration Date	CDOH Plan Approval Number
01/01/2024	

INDEPENDENT AGENCY PLAN REVIEW APPLICATION

Name of Third Party plan review agency:

lan Lehrer-P.E. 0054576

Name of Manufacturer:	Plant street addr	ress:		Plant I.D. Number:
Champion Homes	3200 Ente	rprise Ave		165
Plant Mailing Address:			Plant Telephone:	
3200 Enterprise Ave.			402-362-4 <u>455</u>	
York, NE 68467			Fax No:	
Contact Person:/email			Telephone No:	
Shaun Penne / Spenne@Cha	ampionHomes.com		402-362-4455	
In plant Third Party Inspection A	gency:		Telephone No:	
Nebraska Public Service Com	ım. Housing & RV De	pt.	(402) 471- <u>3101</u>	
Mailing Address: 1200 N St # 300, Lincoln, NE 6	88508		Fax No:	
X 2018 I Code Compliant	Roof Snow Load	100 PSF	Floor Design Load	40 PSF
X 2020 NEC Compliant	Wind Design Speed	115 MPH	Occupancy	R-3
X 2015 IECC Compliant	Seismic Category	С		
2012 IECC Compliant			Elec. >200 amp	
2009 IECC Compliant			3 phase	
			Special Occupancy	
IRC PLANS X	_			
IBC PLANS	_			
Plan Revision	_			
Model Number	05-865-HERBERT		_	
Plan Approval Number	PFS 500206OC		_	
Expiration Date	1/1/2024		_	
Square footage 1856	;			
Unfinished Sqft	_			
Unfinished Area fee = \$0.10/ s	- sa.ft.			
Oversight review fee=\$0.15/so	-	•		
_	minimum)	•		
(φ100.001	<i></i>	•		
Colorado Division of Housing Use only				יַ
] 				
Colorado Division of Housing and o.k. to release plans	oversight	Initials		i -1
l		Date		<u> </u>
L				





"OC" (On-site Construction) Form

Please read below before signing form.

Please See Attached Document at bottom of form for Specific plan and Manufacturer information.

To: The Local Authority Having Jurisdiction (LAHJ) or other DOH approved third party inspection agency.

By signing this form, you confirm that you have received and reviewed this form, and acknowledge that the identified components below are required to complete the construction of this modular structure onsite within your jurisdiction.

Building Official Responsibility

Please check the box labeled "Accept" and initial to confirm that you will take responsibility for inspections of the "OC" Inspection Items on behalf of the DOH. You also acknowledge that it will be done to the DOH approved plans.

If you would like to defer inspection of the "OC" Inspection Items back to the DOH, please check the box labeled "Defer Inspection".

ATTENTION

"On-site Construction" or "OC" means on-site construction or modification of the factory-built structure that directly relates to the durability, quality, and safety; that is completed at the installation "site" as defined by section 24-32-3302(33), C.R.S.; using components not installed at the manufacturer's location; and to complete the compliance of that structure as reflected in the Division of Housing approved plans. These items do not include the component(s) required for setting and securing the structure for its installation.

Fire Safety Official Responsibility (if applicable)

The DOH defers the requirement of any fire protection system for all modular IBC (Section 901.2) and IRC (Section R313) structures as follows:

An automatic fire sprinkler system shall be installed in buildings (IBC) OR one and two family dwellings and townhouses (IRC) OR Tiny homes as required by the local jurisdiction where the structure or home will be set. Final tests required by this Section shall be approved by a certified inspector. The inspector must be either an employee of the fire department having jurisdiction or another qualified individual with prior approval of the Colorado Division of Fire Prevention & Control.

Wild Fire mitigation requirements will be deferred for (IBC) OR one and two family dwellings and townhouses (IRC) OR Tiny homes as required by the local jurisdiction where the structure or home will be set. Final inspections required by locals shall be approved by a certified inspector. The inspector must be either an employee of the fire department having jurisdiction or another qualified individual with prior approval of the Colorado Division of Fire Prevention & Control.







JULY 2023

Please confirm if the LAHJ requires a fire protection system and/or wild fire mititgation for this modular structure. If so, please indicate if the inspection will be completed by a fire department (identify which one) or whether it will be completed by the Colorado Division of Fire Prevention & Control.

Manufacturer Responsibility

The registered manufacturer is responsible for manufacturing a structure that is compliant with our <u>Administrative Rules</u> (CCR 1302-14). If items in the factory have not been completed, only to be completed in the field, you are still responsible for ensuring they have been completed for compliance. Please sign below that you have received this letter and acknowledge the items listed are to complete compliance of the structure, and items are to be inspected and passed for compliance in order to meet Rule 1.13.1 and section 24-32-3311(4), Colorado Revised Statutes (C.R.S.).

ATTENTION

A DOH issued insignia (silver for residential or blue for nonresidential or pink for tiny homes or black for multi-family) certifying its construction cannot be affixed to the structure until all "OC" items are completed on site and pass inspection. The same applies to modular structures manufactured by a certified manufacturer.

Acknowledge Receipt and Understanding

Normal permits and fees for these site work inspections are to be per the local jurisdiction.

State approved plans for Factory-Built Construction may be obtained from the Builder/Manufacturer.

A copy of this completed form is included with the DOH approved plans and must be included with the installation instructions and shipped with the unit. If the completed form has been damaged or lost during shipping, the manufacturer or its representative can obtain a copy from the DOH.

Before any inspection is scheduled at the on-site location or Installation Authorization (required for modular homes and multi-family structures) is issued by the DOH, this form will be required to be signed and dated by the Building Official, or Approved Third Party Agent, or Fire Safety Official (if applicable), and submitted to the DOH.

The DOH approved OC form will be included with the approved spec file, with the DOH Plan Reviewer signature below and their plan approval stamp on the page(s) with the OC listed items to be completed at the site location. That approved OC form should be submitted to the appropriate parties described in this form and submitted back to the DOH before any inspection is scheduled at the onsite location or Installation Authorization (required for modular homes and multi-family structures) is issued.

DOH Plan Reviewer Name	_
H = H = H	
DOH Plan Reviewer Signature	
Date Approved 09/25/23 Contact email:	







JULY 2023

Building Department Representitive Printed Name_		
Building Department Representitive Signature		
Title		
Date		
Accept Defer Inspection	Contact emai	il:
If applicable:		
Fire Safety Official Printed Name		
Fire Safety Official Signature		Date
Contact email:		
Is a fire protection system required? (check one)	Required	Not Required
If required, the inspection is to be performed by (c	heck one):	
Fire Department: (NAME)		
OR		
Colorado Division of Fire Prevention & Cont	rol	
Manufacturer's Authorized Quality Assurance Repre	sentative	
Printed Name Champion Homes		-
Manufacturer's Authorized Quality Assurance Repre	sentative	
Signature Kevin Stephens	Date08/	/28/2023
Contact email: KStephens@ChampionHomes.com		
If the inspection has been deferred and the manufa Agency to inspect the "OC" items on behalf of DOH		
Approved Third Party Agent Printed Name		
Approved Third Party Agent Signature		Date
Contact email:		









Verify Inspection(s) Completed

Once you have completed all of your assigned inspections identified in this form and they have passed for compliance, please sign and date below.

Building Department Representitive Printed Name	
Building Department Representitive Signature	
Date	
Contact email:	
Or	
Approved Third Party Agent Printed Name	<u>-</u>
Approved Third Party Agent Signature	Date
Contact email:	
Fire Protection Systems (if applicable)	
Fire Safety Official Printed Name	
Fire Safety Official Signature	Date
Contact email:	

Please direct questions to manufactured.plans@state.co.us







JULY 2023

The following is based on information provided to the Division of Housing (DOH) and may be modified based on the actual findings of the field inspection.

DATE: 09/11/2023

MANUFACTURER: Champion Home Builders ID NO.: 165

CONTACT: Chris Walker PHONE NO.: 402-362-4455

MODEL NO.: 05-865-HERBERT DOH P/A NO.: R-0005707OC

INSPECTION REQUIREMENTS: Check on site:

"OC" Inspection Items

- Insulate basement/crawl wall to specifications (ResCheck) (Local inspection required)
- Basement/Stairwell construction-separate (Local inspection needed.)
- Complete waste & water line connections. (Local inspection required)
- Field install gas pipes serving furnace, water heater, ect. (Local inspéction required)
- Air Conditioner outlet installed for future use (Local inspection required)
- Surge protector device & Emergency / Disconnect Service Installed On-Site by others (Local inspection required)
- Thermal expansion tank installed OSBO (Local inspection required)
- Check property lines and any adjacent buildings of minimum allowable setback distances (5' minimum)







JULY 2023

Model Number: 05-865-HERBERT

Residential (IRC) & Tiny Home Plan Submission Checklist

A full plan set submission to the Colorado Division of Housing includes the following: (Electronic Plan Submissions Only)

Submitted	Document Type							
V	Plan Review Payment through Salesforce							
	Plan Set Package							
	Architectural Plan Set							
V	 Initialed and signed copy of the Plan Submission Checklist confirming applicable documents have been included in the plan package. 							
V	 Index of submitted plan package Can be a separate document or clearly denoted on cover page 							
	• Site location where structure is to be installed, and Local Authority Having Jurisdiction, or designate the structure as lot model with design loads that are specific for the area the home can be installed, and a minimum setback distance noted for fire separation requirements. If site location is known, a site plan, set back distances to lot lines or other structures, and local AHJ Wildfire Mitigation area requirements (if any) are required to determine fire separation requirements for structure. If structure is to be set in a location where there is no local authority having jurisdiction or lot model, at a minimum, the design loads must comply with 8 CCR 1302-14, Rule 2.2.1.							
	 Code Analysis Design Codes Wind, and Snow Loads (must meet local AHJ and CDOH minimums) Seismic and Wind Exposure category Type of Fire suppression system if applicable (factory installed or on site) If location is known, clearly denote on code analysis if the jurisdiction require a fire suppression system. If one is required and any of the installation is to be in-plant, then it must comply with Colorado Division of Fire Safety & Control Rules (8 CCR 1507-11) & a CORI shall accompany the units throughout the process. 							
Ø	 List of items to be completed on site OC Form included that complies with 8 CCR 1302-14, Rules 1.19, 4.17.1.1, and C.R.S. 24-32-3311(1)(a.7) 							
Ŋ	 Architectural plans with applicable details Floor Plan for Each Level Room Use Specification Window and Door Schedules Elevations Section Drawings (Full and at Stairs) 							







Division of Housing JULY 2023

	Division of Housing JULY 2023
V	 Fire Rated Assembly Details (If applicable) Assemblies not exempt in section R302 to be fire rated or other sections in the code, need to have details showing compliance with section R302 of the IRC for separation of dwellings, fire separation distances, and/or floors. Must comply with the testing standards of either ASTM E119 or UL263 or section 703.3 of the IBC. If section 722 of the IBC has been opted for compliance, the design must be approved through a Colorado Registered Fire Protection engineer.
	Structural Framing Plans
V	 Components Floor Assemblies Wall Assemblies Roof Assemblies Ceiling Assemblies Headers, Beams and Columns Proposed Foundation Braced Wall line details, and tie down equipment with locations that are not specifically addressed in approved installation manual. Construction components exceeding section R301 of the IRC, shall have plans stamped by a Colorado Registered Design Professional.
	MEP Plan Sheets
₩.	 Mechanical System Plans Exhaust Locations Whole home ventilation systems
V	 Electrical System Plans Fixtures, load calculations, panel/circuit schedule with breaker and wire sizing, symbols legend, etc.
u	 Plumbing System Plans (Field installed OSBO from a certified local plumber) Service water piping with piping location, insulation and size Fixture types and locations Isometric for DWV, indicate pipe sizes
V	 Gas System Plans (Field installed OSBO from a certified local installer) Gas Isometric with distances and BTU ratings of appliances it serves Piping material and sizes, service pressure ratings
	Spec Set Package
V	Spec Cover Sheet
Ø	 Copy of the "OC" Inspection letter denoting the "OC" inspection items listed on the submitted plans. Information from the site address on the first page to the "factory authorized representative" portion to the date must be filled in by the factory, except for the CDOH P/A NO (DOH assigned).
Ø	 Engineered/Certified Component Details Engineered and stamped truss details by a State of Colorado professional designed per TPI 1 - 2014 per IRC 2018. Include correct loading and wind speed & exposure, etc. Tiny Home chassis must be engineer approved or certified by NHTSA
	Energy Compliance







Division of Housing JULY 2023

	30L1 2023
Ø	 REScheck (signed) Use appropriate version 2015 (or 2012, 2009 based on local adoption) Use the Colorado city where the building will be installed (If site location is not a selection on REScheck, list exact location on Construction Site information box) If a REScheck is omitted and the prescriptive method is opted for use, please clearly denote on plans a table showing the information depicted in the IECC, Section R103.2 and applicable information per 8 CCR 1302-14, Rule 2.7
Ø	 HVAC System Plans Load calculations for equipment sizing (Manual J) Equipment size listed and meets or exceeds load calculation with deration (Manual S) Supply and return air sizing and plans (Manual D) Site information must match information provided on the REScheck

The Colorado Division of Housing plan review does not begin until the entire plan submission is received.

Applicant must sign below acknowledging submittal checklist has been read and all applicable documents have been submitted for review and any changes to plans require plans to be resubmitted for review, and approved by DOH before construction. All DOH plans are subject to field inspection. Additional information not included in this general list may be requested by DOH plan reviewers to complete review.

Shaun Penne	9/11/2023
X	Date:

For additional plan review requirements, questions, or concerns, please reach out to our staff at:

FB/FBNR
manufactured.plans@state.co.us
Tiny Homes
dola_tinyhomes@state.co.us





INDEX

- HVAC Calcs
- Truss Print
- Overall IRC 2018 Drawing Index
- FD01.01 General Notes
- SP01.01A High Snow Span Table
- FA01.01 General Notes / Fastener Substitution
- ResCheck Efficiency

Champion Home Builders 3200 Enterprise Ave. York, NE 68467



Job: 05-865-HERBERT

Date: 9/11/23

By: AMS of Indiana, Inc.

Project Information

For: Champion Home Builders

3200 Enterprise Ave., York, NE 68467

<u>Site:</u> 18195 Hwy 131 Yampa, CO 80483

	Design Information					
Htg Clg Infiltration						
	Outside db (°F)	-15	85	Method		Simplified
	Inside db (°È)	70	75	Construction quality		Average
	Design TD (°F)	85	10	Fireplaces		0
	Daily range	-	Н	·		
	Inside humidity (%)	50	50			
	Moisture difference (gr/lb)	71	-35			

HEATING EQUIPMENT

COOLING EQUIPMENT

iviake	Generic			iviake	Generic		
Trade				Trade			
Model	AFUE 100			Cond	SEER 14.0		
AHRI ref				Coil			
				AHRI ref			
Efficiency		100 AFUE		Efficiency		12.2 EER, 14 SEER	
Heating inpu	ıt	11.1	kW	Sensible cod	oling	10850	Btuh
Heating outp	out	37883	Btuh	Latent coolir	ng	4650	Btuh
Temperature	e rise	66	°F	Total cooling	j	15500	Btuh
Actual air flo	W	692	cfm	Actual air flo	W	692	cfm
Air flow facto	r	0.021	cfm/Btuh	Air flow facto	or	0.060	cfm/Btuh
Static pressu	ire	0.30	in H2O	Static pressu	ıre	0.30	in H2O
Space therm				Load sensib	le heat ratio	1.00	

ROOM NAME	ROOM NAME Area (ft²)		Clg load (Btuh)	Htg AVF (cfm)	Clg AVF (cfm)
M BA	90	1025	161	22	10
UTILITY	120	2171	217	46	13
C1	39	0	0	0	0
KIT\DIN\FAM\LIV	781	8415	5218	178	315
B1	232	3254	2152	69	130
B2	170	1580	1329	33	80
B3	170	2598	1363	55	82
B4	153	2473	806	52	49
A	21	0	0	0	0
BA	55	472	55	10	3
CRAWL	1833	^l 10741	^l 148	227	9

Bold/italic values have been manually overridden

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.



Entire House Other equip loads Equip. @ 0.90 RSM Latent cooling	3666	32730 5153	11449 606 10850 0	692	692
TOTALS	3666	37883	10850	692	692

Bold/italic values have been manually overridden Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.



Job: **05-865-HERBERT** Date: 9/11/23 AMS of Indiana, Inc.

Project Information

For: Champion Home Builders

3200 Enterprise Ave., York, NE 68467

		Design Co	onditions		
Location: Craig-Moffat, CO, US Elevation: 7687 ft Latitude: 40°N	Yampa, CO		Indoor: Indoor temperature (°F) Design TD (°F) Relative humidity (%)	Heating 70 85 50	Cooling 75 10 50
Outdoor:	Heating	Cooling	Moisture difference (gr/lb)	70.6	-34.6
Dry bulb (°F) Daily range (°F) Wet bulb (°F) Wind speed (mph)	-15 - - 15.0	85 38 (H) 58 7.5	Infiltration: Method Construction quality Fireplaces	Simplified Average 0	


Heating

Component	Btuh/ft²	Btuh	% of load
Walls Glazing Doors Ceilings Floors Infiltration Ducts Piping Humidification	Btuh/tt² 6.1 28.9 24.6 1.7 1.7 3.2	11922 5292 2071 3116 3116 7214 0 0	31.5 14.0 5.5 8.2 19.0 0 0
Ventilation Adjustments Total		5153 0 37883	13.6 100.0



Cooling

Component	Btuh/ft ²	Btuh	% of load
Walls	0.1	106	0.9
Glazing	36.5	6681	55.4
Doors	3.6	306	2.5
Ceilings	0.7	1321	11.0
Floors	0	0	0
Infiltration	0.2	455	3.8
Ducts		0	0
Ventilation		606	5.0
Internal gains		2580	21.4
Blower		0	0
<u>A</u> djustments		0	
Total		12055	100.0



Latent Cooling Load = 0 Btuh

Overall U-value = 0.051 Btuh/ft²-°F, Window / Floor Area = 5.0 %

WARNING: window to floor area ratio = 5.0% - less than 5%.

Bold/italic values have been manually overridden



 ₩

 wrightsoft



Component Constructions Entire House

Job: 05-865-HERBERT

Date: 9/11/23

AMS of Indiana, Inc.

Project Information

For: Champion Home Builders

3200 Enterprise Ave., York, NE 68467

		Design Co	onditions		
Location: Craig-Moffat, CO, US Elevation: 7687 ft Latitude: 40°N	Yampa, CO		Indoor: Indoor temperature (°F) Design TD (°F) Relative humidity (%)	Heating 70 85 50	Cooling 75 10 50
Outdoor:	Heating	Cooling	Moisture difference (gr/lb)	70.6	-34.6
Dry bulb (°F)	-15	85	Infiltration:		
Daily range (°F)	-	38 (H)	Method	Simplified	
Wet bulb (°F)	-	58	Construction quality	Average	
Wind speed (mph)	15.0	7.5	Fireplaces	0	

Construction descriptions	Or	Area ft²	U-value Btuh/ft²-°F	Insul R ft²-°F/Btuh	Htg HTM Btuh/ft²	Loss Btuh	Clg HTM Btuh/ft²	Gain Btuh
Walls								
12F-0sw: Frm wall, vnl ext, 3/8" wood shth, r-21 cav ins, 1/2" gypsum	n	202	0.065	21.0	5.53	1113	0.09	18
board int fnsh, 2"x6" wood frm, 16" o.c. stud	е	431	0.065	21.0	5.53	2379	0.09	38
	S	210	0.065	21.0	5.52	1163	0.09	18
	W	370	0.065	21.0	5.52	2047	0.09	33
	all	1213	0.065	21.0	5.52	6701	0.09	106
Bg wall, light dry soil, 2"x4" wood int frm, concrete wall, r-12 cav ins, 8" thk	n	115	0.083	12.0	7.05	811	0	0
	е	255	0.083	12.0	7.05	1799	0	0
	S	115	0.083	12.0	7.05	811	0	0
	W	255	0.083	12.0	7.05	1799	0	0
	all	740	0.083	12.0	7.05	5221	0	0
Partitions (none)								
Windows								
DftWind: 3 glazing, clr low-e outr, 1/2" gap, insulated vinyl frm mat, clr	n	8	0.340	0	28.9	217	9.18	69
low-e mid, argon gas, 1/4" thk, clr innr; NFRC rated (SHGC=0.30); 6.67 ft	е	38	0.340	0	28.9	1084	31.7	1188
head ht	s	20	0.340	0	28.9	566	15.9	311
	W	119	0.340	0	28.9	3425	31.7	3754
	all	183	0.340	0	28.9	5292	29.1	5321
Doors								
11P0: Door, mtl pur core type	n	21	0.290	10.5	24.6	518	3.64	76
	е	42	0.290	10.5	24.6	1035	3.64	153
	W	21	0.290	10.5	24.6	518	3.64	76
	all	84	0.290	10.5	24.6	2071	3.64	306
Ceilings								
16B-50ad: Attic ceiling, asphalt shingles roof mat, r-50 ceil ins, 1/2" gypsum board int fnsh		1833	0.020	50.0	1.70	3116	0.72	1321
Floors 21A-32t: Bg floor, light dry soil, 4' depth		1833	0.020	0	1.70	3116	0	0
Bold/italic values	have be	een manua	lly overridden					



2023-Sep-11 10:38:57

05-865-HERBERT Date: 9/11/23 AMS of Indiana, Inc.

Project Information

For:

Champion Home Builders 3200 Enterprise Ave., York, NE 68467

Notes: The furnace output has been adjusted for elevation.

Design Information

Weather: Craig-Moffat, CO, US

Winter Design Conditions

Summer Design Conditions

Outside db Inside db	-15 70	°F °F	Outside db Inside db	85 °F 75 °F	
Design TD	85	°F	Design TD Daily range	10 °F H	
			Relátive humidity Moisture difference	50 % -35 gr/lb	,

Heating Summary

Sensible Cooling Equipment Load Sizing

Structure	32730	Btuh	Structure	11449	Btuh
Ducts	0	Btuh	Ducts	0	Btuh
Central vent (73 cfm)	5153	Btuh	Central vent (73 cfm)	606	Btuh
Outside air			Outside air		
Humidification	0	Btuh	Blower	0	Btuh
Piping Equipment load	0	Btuh			
Equipment load	37883	Btuh	Use manufacturer's data	r	1
			Rate/swing multiplier	0.90	
Infiltration	1		Equipment sensible load	10850	Btuh

Infiltration

Method Construction quality		Simplified Average	Latent Cooling Equipmen	it Load S	Sizing
Fireplaces		0	Structure	228	Btuh
			Ducts Central vent (73 cfm)	-1296	Btuh Btuh
Area (ft²)	Heating 3666	Cooling 3666	Outside air Equipment latent load	0	Btuh
Volume (ft³)	21994 0.28	21994 0.15		10850	Dtub
Air changes/hour Equiv. AVF (cfm)	103	0.15 55	Equipment Total Load (Sen+Lat) Req. total capacity at 0.70 SHR	1.3	ton

Heating Equipment Summary

Cooling Equipment Summary

Make Trade	Generic			Make Trade	Generic		
Model AHRI ref	AFUE 100			Cond Coil	SEER 14.0		
Efficiency Heating inpute Heating outpute Temperature Actual air flow factor Static pressuus Space them	out e rise w or ure	100 11.1 37883 66 692 0.021 0.30	AFUE kW Btuh °F cfm cfm/Btuh in H2O	AHRI ref Efficiency Sensible cor Latent cooling Actual air flo Air flow facto Static presso Load sensib	ng g w or	12.2 EER, 14 SEER 10850 4650 15500 692 0.060 0.30 1.00	Btuh Btuh Btuh cfm cfm/Btuh in H2O

Bold/italic values have been manually overridden

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.





Job: **05-865-HERBERT**

9/11/23 Date:

1 2 3 4 5			6.0 0	370.4 ft	House 0 ft 4864. 3665.	6 ft²	9.3 x 9.8 ft 90		8 ft 304.1 90.1	0 ft² 2 ft² 2 ft²			
	Type of	Const.,	Panel	н	ТМ	Area or		Btuh		Area or		Btuh	
	Exposure	Number	Faces	Htg.	Clg.	Length	Heating	S-Clg	L-Clg	Length	Heating	S-Clg	L-Clg
6	Wall Glaz Door Wall Wall Glaz Wall Wall Glaz Wall Glaz Toor Wall Flor	12F-Osw DftWind 11P0 Bg wall, light dry s 12F-Osw DftWind 11P0 Bg wall, light dry s 12F-Osw DftWind Bg wall, light dry s 12F-Osw DftWind Bg wall, light dry s 12F-Osw DftWind 11P0 Bg wall, light dry s 16B-50ad 21A-32t	n n n n e e e e s s w w w	5.52 28.90 24.65 7.05 5.52 28.90 24.65 7.05 5.52 28.90 24.65 7.05 1.70 1.70	0.09 9.18 3.64 0.00 0.09 31.67 3.64 0.00 0.09 15.89 0.00 0.09 31.67 3.64 0.00 0.72 0.00	230 8 21 115 510 38 42 255 230 115 510 119 21 255 1833 1833	1113 217 518 811 2379 1084 1035 1799 1163 566 811 2047 3425 518 1799 3116 3116	18 69 76 0 38 1188 153 0 18 311 0 33 3754 76 0 1321 0		78 8 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	390 217 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	69 0 0 0 0 0 0 0 0 0 0 0 0 0 0	
	Infiltration	Heating Load (Btuh)		Effect	0.28	WAR	7214			WAR	253		
12		Sensible Load (Btuh)		ACH	0.15	1.00		455		0.04		16	
<u></u>		Latent Load (Btuh)							-972				
13	Internal	al a Occupants at 230 and 200 Btuh b Scenario number c Default Adjustments d Custom Appliances e Plants				6		1380 1200 0	1200 0 0	0		0 0 0	0 0 0
14	Subtotals			Sum lines 6 th	rough 12		32730	11449	228		1025	161	
1.5	Duct	EHLF & ESGF		0	0		0	0			0	0	
15	Loads						0				0		
16	Ventilation Loads	Vent Cfm	73	E Cfm	73		5153	606	-1296				
17	Winter Humidificatio	n Load		Gal/Day	0		0						
18	Piping Load						0						
19	Blower Heat							0					
20	AED Excursion & La	tent Moisture Migration Lo	ad					1360				0	
21	Total Load	-		Sum lines 13 th	nrough 19		37883	12055	0		1025	161	



Job: **05-865-HERBERT**

9/11/23 Date:

1 2 3 4 5	Room Dimensions (oosed Wall Gross Wall Area (SqFt) (Ft) and Floor Plan Area (S) and Gross Ceiling Area (S	qFt) SqFt)			8.0 1.0 x 1 0	22.9 ft	120.	0 ft² 0 ft² 0 ft²	8.0 8.3 0	ft x 4.8 ft	39.	0 ft² 2 ft² 2 ft²
	Type of	Const.,	Panel	H-	тм	Area or		Btuh		Area or		Btuh	
	Exposure	Number	Faces	Htg.	Clg.	Length	Heating	S-Clg	L-Clg	Length	Heating	S-Clg	L-Clg
6	Wall Glaz Door Wall Wall Glaz Door Wall Wall Glaz Wall Glaz Flor	12F-0sw DftWind 11P0 Bg wall, light drys 12F-0sw DftWind 11P0 Bg wall, light drys 12F-0sw DftWind Bg wall, light drys 12F-0sw DftWind Bg wall, light drys 12F-0sw DftWind 11P0 Bg wall, light drys 16B-50ad 21A-32t	n n n n e e e e s s s w w w	5.52 28.90 24.65 7.05 5.52 28.90 24.65 7.05 5.52 28.90 24.65 7.05 1.70	0.09 9.18 3.64 0.00 0.09 31.67 3.64 0.00 0.09 15.89 0.00 0.09 31.67 3.64 0.00 0.72 0.00	36 0 21 0 140 0 0 0 0 0 0 0 0 0 0 0 0 0 0	83 0 518 0 773 0 0 0 0 0 0 0 0 0 0 0	1 0 76 0 12 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	
	Infiltration	Heating Load (Btuh)		Effect	0.28	WAR	572			WAR	0		
12		Sensible Load (Btuh)		ACH	0.15	0.08		36		0		0	
<u> </u>		Latent Load (Btuh)			00								
13	Internal	a Occupants at 230 and b Scenario number c Default Adjustments d Custom Appliances e Plants	200 Btuh			0		0	0 0	0		0 0	0 0 0
14	Subtotals			Sum lines 6 th	rough 12		2171	217			0	0	
	Duct	EHLF & ESGF		0	0		0	0			0	0	
15	Loads					0				0			
16	Ventilation Loads	Ventilation Loads Vent Cfm 73 E Cfm 7											
17	Winter Humidification	on Load		Gal/Day	0								
18	Piping Load												
19	Blower Heat												
20	AED Excursion & La				-4				-1				
21	Total Load		,	Sum lines 13 th	rough 19		2171	217			0	0	



Job: **05-865-HERBERT**

9/11/23 Date:

1 2 3 4 5	Room Dimensions	oosed Wall Gross Wall Area (SqFt) (Ft) and Floor Plan Area (S .) and Gross Ceiling Area (8.0 1.0 x 7 0	54.5 ft	INFAMLIV 5 ft 1052. 781. 781.	4 ft²	8.0 16.0 x 0	30. ft 14.5 ft	B1 5 ft 488. 232. 232.	Oft²		
	Type of	Const.,	Panel	H1	ГМ	Area or		Btuh		Area or		Btuh	
	Exposure	Number	Faces	Htg.	Clg.	Length	Heating	S-Clg	L-Clg	Length	Heating	S-Clg	L-Clg
6	Wall Glaz Door Wall Wall Glaz Door Wall Wall Glaz Wall Claz Toor Wall Flor	12F-0sw DftWind 11P0 Bg wall, light drys 12F-0sw DftWind 11P0 Bg wall, light drys 12F-0sw DftWind Bg wall, light drys 12F-0sw DftWind 11P0 Bg wall, light drys 12F-0sw DftWind 21A-32t	n n n n e e e e s s s w w w	5.52 28.90 24.65 7.05 5.52 28.90 24.65 7.05 5.52 28.90 24.65 7.05 1.70 1.70	0.09 9.18 3.64 0.00 0.09 31.67 3.64 0.00 0.09 15.89 0.00 0.09 31.67 3.64 0.00 0.72 0.00	0 0 0 0 284 38 42 0 0 0 152 49 21 0 781 0	0 0 0 0 1130 1084 1035 0 0 0 451 1426 518 0 1328 0	0 0 0 0 18 1188 153 0 0 0 7 1563 76 0 563 0		116 0 0 0 0 0 0 0 0 0 128 30 0 0 232 0	641 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	10 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	
	Infiltration	Heating Load (Btuh)		Effect	0.28	WAR	1417			WAR	793		
12		Sensible Load (Btuh)		ACH	0.15	0.20		89		0.11		50	
		Latent Load (Btuh)											
13	Internal	a Occupants at 230 and b Scenario number c Default Adjustments d Custom Appliances	200 Btuh			1		230 1200 0	200	2		460 0 0	400
1/	Subtotals	e Plants		Sum lines 6 th	rough 12		8415	5218	0		3254	2152	0
14	Duct	EHLF & ESGF		Summesom			0415	0			3234	0	
15	Loads							U	0		U	0	0
16	Ventilation Loads												-
17	Winter Humidification		<u> </u>	Gal/Day	0								
18	Piping Load			,									
19							-		-				-
20		AED Excursion & Latent Moisture Migration Load						119				499	
21	Total Load			Sum lines 13 th	rough 19		8415	5218		-	3254	2152	



Job: **05-865-HERBERT**

9/11/23 Date:

1 2 3 4 5	Room Dimensions (oosed Wall Gross Wall Area (SqFt) (Ft) and Floor Plan Area (S) and Gross Ceiling Area (SqFt) SqFt)			8.0 11.8 x 0	11.8 ft 14.5 ft	32 8 ft 420. 170. 170.	4 ft²	8.0 11.8 x 0	26. ft 14.5 ft	B3 3 ft 420.0 170.0 170.0	4 ft²
	_Type of	Const.,	Panel	H.	тм	Area or		Btuh		Area or		Btuh	
	Exposure	Number	Faces	Htg.	Clg.	Length	Heating	S-Clg	L-Clg	Length	Heating	S-Clg	L-Clg
6	Wall —Glaz —Door Wall Wall —Glaz —Door Wall Wall —Glaz —Glaz Wall —Glaz —Door Wall —Glaz —Door Wall —Glaz —Door	12F-Osw DftWind 11P0 Bg wall, light drys 12F-Osw DftWind 11P0 Bg wall, light drys 12F-Osw DftWind Bg wall, light drys 12F-Osw DftWind 11P0 Bg wall, light drys 12F-Osw DftWind 11P0 Bg wall, light drys 16B-50ad 21A-32t	n n n n e e e e s s s w w w	5.52 28.90 24.65 7.05 5.52 28.90 24.65 7.05 5.52 28.90 24.65 7.05 1.70 1.70	0.09 9.18 3.64 0.00 0.09 31.67 3.64 0.00 0.09 31.67 3.64 0.00 0.72 0.00	0 0 0 0 0 0 0 0 0 0 0 94 20 0 0 0	0 0 0 0 0 0 0 0 0 0 0 411 566 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		0 0 0 0 0 0 0 0 116 0 0 94 20 0 0 0	0 0 0 0 0 0 0 641 0 0 411 566 0 0 0	0 0 0 0 0 0 0 0 0 7 620 0 0 123 0	
	Infiltration	Heating Load (Btuh)		Effect	0.28	WAR	305			WAR	682		
12		Sensible Load (Btuh)		ACH	0.15	0.04		19		0.09		43	
		Latent Load (Btuh)			0.10								
13	Internal	a Occupants at 230 and b Scenario number c Default Adjustments d Custom Appliances e Plants	l 200 Btuh			1		230 0 0	200 0 0	1		230 0 0	200
14	Subtotals			Sum lines 6 th	rough 12		1580	1329			2598	1363	
15	Duct	EHLF & ESGF		0	0		0	0			0	0	
15	LUAUS	Loads							0				0
16	Ventilation Loads	Ventilation Loads Vent Cfm 73 E Cfm 75											
17	Winter Humidification	Winter Humidification Load Gal/Day C											
18	Piping Load												
19	Blower Heat												
20	AED Excursion & Latent Moisture Migration Load							327				327	
21	Total Load		;	Sum lines 13 th	rough 19		1580	1329			2598	1363	



Job: **05-865-HERBERT**

9/11/23 Date:

1 2 3 4 5	Ceiling Ht (Ft) and G Room Dimensions (Running Feet of Exposed Wall Ceiling Ht (Ft) and Gross Wall Area (SqFt) Room Dimensions (Ft) and Floor Plan Area (SqFt) Ceiling Slope (Deg.) and Gross Ceiling Area (SqFt)				8.0 10.8 x 0	25.0 ft 14.3 ft	153.	0 ft² 2 ft² 2 ft²	8.0 5.3 0	ft x 4.0 ft	21.	0 ft² 0 ft² 0 ft²
	Type of	Const.,	Panel	H ⁻	ГМ	Area or		Btuh		Area or		Btuh	
	Exposure	Number	Faces	Htg.	Clg.	Length	Heating	S-Clg	L-Clg	Length	Heating	S-Clg	L-Clg
6	Wall Glaz Door Wall Wall Wall Glaz Wall Wall Glaz Wall Glaz Toor Wall Flor	12F-0sw DftWind 11P0 Bg wall, light drys 12F-0sw DftWind 11P0 Bg wall, light drys 12F-0sw DftWind Bg wall, light drys 12F-0sw DftWind Bg wall, light drys 12F-0sw 12F-0sw 21A-32t	n n n n e e e e s s w w w	5.52 28.90 24.65 7.05 5.52 28.90 24.65 7.05 5.52 28.90 24.65 7.05 1.70 1.70	0.09 9.18 3.64 0.00 0.09 31.67 3.64 0.00 0.09 15.89 0.00 0.09 31.67 3.64 0.00 0.72 0.00	0 0 0 0 0 86 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 475 0 0 0 0 522 566 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0	
	Infiltration	Heating Load (Btuh)		Effect	0.28	WAR	650			WAR	0		
12		Sensible Load (Btuh)		ACH	0.15	0.09		41		0		0	
_		Latent Load (Btuh)			50								
13	Internal	a Occupants at 230 and b Scenario number c Default Adjustments d Custom Appliances e Plants	l 200 Btuh			1		230 0 0	200	0		0 0 0	0
14	Subtotals			Sum lines 6 th	rough 12		2473	806			0	0	
	Duct	EHLF & ESGF	-	0	-		0	0	-	-	0	0	
15	Loads								0				0
16	Ventilation Loads	73				-	-						
17	Winter Humidification	on Load	-	Gal/Day	0								
18	Piping Load			<u> </u>									
19	Blower Heat												
20	AED Excursion & La				98				0				
21	Total Load		;	Sum lines 13 th	rough 19		2473	806			0	0	



Job: **05-865-HERBERT**

9/11/23 Date:

1 2 3 4 5	Room Dimensions (oosed Wall Gross Wall Area (SqFt) (Ft) and Floor Plan Area (S and Gross Ceiling Area (S	iqFt) SqFt)			8.0 5.3 x 0	5.3 ft 10.5 ft	BA 3 ft 252. 55. 55.	0 ft² 1 ft² 1 ft²	4.0 63.8 x 0	185. ft 28.8 ft		
	Type of	Const.,	Panel	H ⁻	гм	Area or		Btuh		Area or		Btuh	
	Exposure	Number	Faces	Htg.	Clg.	Length	Heating	S-Clg	L-Clg	Length	Heating	S-Clg	L-Clg
6	Glaz Door Wall	12F-0sw DftWind 11P0 Bg wall, light drys 12F-0sw DftWind 11P0 Bg wall, light drys 12F-0sw DftWind Bg wall, light drys 12F-0sw DftWind Bg wall, light drys 12F-0sw 12F-0sw 21A-32t	n n n n e e e e s s w w w	5.52 28.90 24.65 7.05 5.52 28.90 24.65 7.05 5.52 28.90 24.65 7.05 1.70 1.70	0.09 9.18 3.64 0.00 0.09 31.67 3.64 0.00 0.09 15.89 0.00 0.09 31.67 3.64 0.00 0.72 0.00	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		0 0 0 115 0 0 255 0 115 0 0 255 0 1833	0 0 0 811 0 0 0 1799 0 811 0 0 1799 0 3116		
	Infiltration	Heating Load (Btuh)		Effect	0.28	WAR	136			WAR	2405		
12		Sensible Load (Btuh)		ACH	0.15	0.02		9		0.33		152	
		Latent Load (Btuh)			5.10								
13	Internal	a Occupants at 230 and b Scenario number c Default Adjustments d Custom Appliances e Plants	1200 Btuh			0		0 0 0	0 0	0		0 0	0
14	Subtotals	•		Sum lines 6 th	rough 12		472	55			10741	148	
	Duct	EHLF & ESGF		0	-		0	0			0	0	
15	Loads					0				0			
16	Ventilation Loads	73											
17	Winter Humidification	on Load	-	Gal/Day	0								
18	Piping Load	Piping Load											
19	Blower Heat												
20	AED Excursion & Latent Moisture Migration Load							-1				-3	
21	Total Load		;	Sum lines 13 th	rough 19		472	55			10741	148	



Job: 05-865-HERBERT

Date: 9/11/23

AMS of Indiana, Inc.

Project Information

Champion Home Builders For:

3200 Enterprise Ave., York, NE 68467

Heating Cooling 0.30 in H2O 0.30 in H2O External static pressure 0.06 in H2O 0.06 in H2O Pressure losses Available static pressure 0.24 in H2O 0.24 in H2O Supply / return available pressure 0.178 / 0.062 in H2O 0.178 / 0.062 in H2O Lowest friction rate 0.062 in/100ft 0.062 in/100ft Actual air flow 692 cfm 692 cfm Total effective length (TEL) 389 ft

Supply Branch Detail Table

Name		Design (Btuh)	Htg (cfm)	Clg (cfm)	Design FR	Diam (in)	HxW (in)	Duct Matl	Actual Ln (ft)	Ftg.Eqv Ln (ft)	Trunk
B1	С	1076	34	65	0.062	6.0	0x 0	VIFx	27.3	260.0	st2
B1-A	С	1076	34	65	0.062	6.0	0x 0	VIFx	36.8	250.0	st2
B2	С	1329	33	80	0.064	6.0	0x 0	VIFx	64.5	215.0	st2
B3	С	1363	55	82	0.070	6.0	<i>0</i> × <i>0</i>	VIFx	72.3	180.0	st1
B4	h	2473	52	49	0.092	6.0	0x 0	VIFx	53.8	140.0	st1
BA	h	472	10	3	0.073	6.0	0x 0	VIFx	74.8	170.0	st1
CRAWL	h	3580	76	3	0.122	6.0	<i>0</i> × <i>0</i>	VIFx	5.3	140.0	st2
CRAWL-A	h	3580	76	3	0.091	6.0	0x 0	VIFx	45.0	150.0	st1
CRAWL-C	h	3580	76	3	0.063	6.0	0x 0	VIFx	56.8	225.0	st2
KIT\DIN\FAM\LIV	С	870	30	53	0.090	6.0	0x 0	VIFx	21.8	175.0	st1
KIT\DIN\FAM\LIV-A	С	870	30	53	0.086	6.0	0x 0	VIFx	31.3	175.0	st1
KIT\DIN\FAM\LIV-C	С	870	30	53	0.086	6.0	0x 0	VIFx	45.8	160.0	st1
KIT\DIN\FAM\LIV-D	С	870	30	53	0.062	6.0	0x 0	VIFx	53.0	235.0	st2
KIT\DIN\FAM\LIV-E	С	870	30	53	0.062	6.0	0x 0	VIFx	42.3	245.0	st2
KIT\DIN\FAM\LIV-F	С	870	30	53	0.087	6.0	0x 0	VIFx	38.3	165.0	st1
MBA	h	1025	22	10	0.114	6.0	0x 0	VIFx	5.3	150.0	st2
UTILITY-A	h	2171	46	13	0.097	6.0	0x 0	VIFx	8.0	175.0	st1

Supply Trunk Detail Table

Name	Trunk Type	Htg (cfm)	Clg (cfm)	Design FR	Veloc (fpm)	Diam (in)	HxW (in)	Duct Material	Trunk
st1	Peak AVF	358	361	0.070	742	10.1	5 x 14	ShtMetl	
st2	Peak AVF	335	331	0.062	689	10.1	5 x 14	ShtMetl	

Bold/italic values have been manually overridden



Return Branch Detail Table

Name	Grille Size (in)	Htg (cfm)	Clg (cfm)	TEL (ft)	Design FR	Veloc (fpm)	Diam (in)	HxW (in)	Stud/Joist Opening (in)	Duct Matl	Trunk
rb1	0x 0	692	692	100.9	0.062	496	16.0	0x 0		VIFx	

Job Truss Type Truss Qty Champion 223 1 N5-1037 29DW 3/12 Flat - 100 @16" 107124 1 M1166701 MONO TRUSS

UFP Industries Inc., Grand Rapids, MI 49525, Tom Craig

8.430 e Jan 4 2021 MiTek Industries, Inc. Mon Aug 9 10:37:40 2021 Page 1 of 1

Copyright © 2021 UFP Industries, Inc. All Rights Reserved




Plate Offsets (X Y)-- [6:0-2-1 0-0-4] [8:0-2-8 0-2-8]

That one of the transfer of th									
LOADING (psf) TCLL 100.0 (Roof Snow=100.0) TCDL 10.0	SPACING- 1-4-0 Plate Grip DOL 1.00 Lumber DOL 1.00 Rep Stress Incr YES	CSI. TC 0.96 BC 0.92 WB 0.66	DEFL. in (loc) l/defl L/d Vert(LL) -0.24 2-8 >694 240 Vert(CT) -0.38 2-8 >447 180 Horz(CT) 0.06 7 n/a n/a	PLATES GRIP MT20 197/144					
BCLL 0.0 *	Code IBC2018/TPI2014	Matrix-RH	, ,	Weight: 47 lb FT = 5%					

LUMBER-

TOP CHORD 2x4 SPF 2100F 1.8E BOT CHORD 2x4 SPF 1650F 1.5E

2x3 SPF No.2 **WEBS**

BRACING-TOP CHORD BOT CHORD

WEBS

Structural wood sheathing directly applied, except end verticals.

Rigid ceiling directly applied or 2-2-0 oc bracing. 1 Row at midpt 5-7

REACTIONS. (lb/size) 2=1350/0-3-8 (min. 0-2-10), 7=1114/Mechanical Max Horz 2=315(LC 6)

Max Uplift2=-582(LC 6), 7=-501(LC 8) Max Grav 2=1675(LC 2), 7=1463(LC 2)

FORCES. (lb) - Maximum Compression/Maximum Tension

1-2=0/33, 2-9=-3447/1605, 3-9=-3426/1618, 3-4=-2064/911, 4-5=-1899/918, 5-6=-123/67, 6-7=-373/245 2-8=-1920/3179, 7-8=-1096/1913 TOP CHORD

BOT CHORD

5-8=-282/657, 3-8=-1369/891, 5-7=-2198/1259


NOTES-

- 1) Wind: ASCE 7-16; Vult=200mph (3-second gust) Vasd=158mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3E) -1-3-12 to 1-8-4, Exterior(2N) 1-8-4 to 11-2-8, Corner(3E) 11-2-8 to 14-2-8 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60 2) TCLL: ASCE 7-16; Pf=100.0 psf (Lum DOL=1.00 Plate DOL=1.00); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this design.
- 4) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 100.0 psf on overhangs non-concurrent with other live loads.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 582 lb uplift at joint 2 and 501 lb uplift at joint 7. 8) This truss is designed in accordance with the 2018 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



The professional engineering seal indicates that a licensed professional engineer has designed the truss under the standards referenced within this document, not necessarily the current state building code. The engineering seal is not an approval to use in a specific state. The final determination on whether a truss design is acceptable under the locally adopted building code rest with the building official or designated appointee.



2801 EAST BELTLINE RD, NE GRAND RAPIDS, MI 49525





[PB]


	irc 2018 - Drawing			
Drawing Number	Description	Calc. No.	Drawing Date	Designed By
General (G)	E)			
GE01.01	CODES, SPECIFICATIONS AND HOME TYPES		09/28/18	SCD
GE02.01	GENERAL NOTES		09/28/18	SCD
GE03.01	ONE STORY CROSS-SECTION		09/28/18	SCD
GE03.02	CAPE CROSS SECTION		09/28/18	SCD
GE03.03	TWO STORY CROSS SECTION		09/28/18	SCD
HVAC (HVA				
HV01.01	MECHANICAL SYSTEMS - GENERAL NOTES		09/28/18	SCD
HV01.02	HVAC RIM JOIST CROSS-OVER, 2x10 OFF-FRAME FLOORS	MH-105	09/28/18	SCD
El 10				
Electrical (00/00/40	000
EL01.01	ELECTRICAL SYSTEM - GENERAL NOTES		09/28/18	SCD
Plumbing (PL)			
PL01.01	PLUMBING SYSTEM - GENERAL NOTES		09/28/18	SCD
Thermal (T.	H)			
TH01.01	ENERGY EFFICIENCY		09/28/18	SCD
Fastening (EA)			
FA01.01	GENERAL NOTES & FASTENING SUBSTITUTION	FA-100	09/28/18	SCD
FA01.02	FLOOR SYSTEM & ROOF SYSTEM	171 100	09/28/18	SCD
FA01.03	EXTERIOR WALLS & INTERIOR WALLS		09/28/18	SCD
FA02.01	GYPSUM FASTENING / FOAM ONLY OPTION		09/28/18	SCD
Foundation	1 (FD)			
FD01.01	GENERAL NOTES	MD-100	09/28/18	SCD
FD01.02	RANCH MATE LINE DESIGN	MD-105; MD-105.1	09/28/18	SCD
FD01.03	CAPE & 2 STORY MATE LINE DESIGN	MD-110; MD-110.1	09/28/18	SCD
FD02.01	CRAWLSPACE (1, 1.5 & 2 STORY)		09/28/18	SCD
FD02.02	FULL BASEMENT (1, 1.5 & 2 STORY)		09/28/18	SCD
FD02.03	END & SIDE WALL PORCHES (OFF-FRAME FOUNDATION)	MD-120	09/28/18	SCD
Floor (FL)				
FL01.01	FLOOR CONSTRUCTION - GENERAL NOTES		09/28/18	SCD
FL02.01	FLOOR W/ 2x JOISTS - FRAMING & PLAN NOTES	MF-100	09/28/18	SCD
			09/28/18	SCD
FL02.02	STAIR OPENING FRAMING - W/ 2x LUMBER JOISTS	MF-110		SCD
FL02.03	STAIR DETAILS		09/28/18	
FL03.01	FLOOR - OPEN JOIST 2000, FRAMING PLAN & NOTES	MF-100	09/28/18	SCD
FL03.02	FLOOR - OPEN JOIST 2000, FRAMING DETAILS	MF-120	09/28/18	SCD
Wall (WA)				
WA01.01	WALL CONSTRUCTION (GENERAL NOTES)		09/28/18	SCD
WA02.01	RANCH WALL CONSTRUCTION		09/28/18	SCD
WA02.02	1½ & 2 STORY SIDEWALLS		09/28/18	SCD
WA02.03	1½ & 2 STORY MATE WALLS		09/28/18	SCD
WA02.04	1½ STORY GABLE END WALLS		09/28/18	SCD
WA03.01	STUD CHARTS - 1, 1½ & 2 STORY		09/28/18	SCD
WA03.02	INTERIOR NON-LOAD BEARING WALLS		09/28/18	SCD
WA03.51	HIGH WIND STUD CHARTS	MW-100	09/28/18	SCD
WA05.01	RANCH, UPPER 2 STORY SIDEWALL HEADERS	MW-105	09/28/18	SCD
WA05.01		MW-105		
	1½ & LOWER 2 STORY SIDEWALL HEADERS		09/28/18	SCD
WA05.11	RANCH, UPPER 2 STORY LVL HEADERS	MW-150	05/11/16	SCD
WA05.12	1½ & LOWER 2 STORY LVL HEADERS	MW-150	05/11/16	SCD
WA05.51	HIGH WIND SIDEWALL HEADERS	MW-105	09/28/18	SCD
WA06.01	LAY FLAT & END WALL HEADERS / SILLS	MW-105	09/28/18	SCI

Wall (WA) - CONTINUED			
WA08.01	JACK & JAMB WALL STUDS	MW-110	09/28/18	SCD
WA08.51	HIGH WIND JAMB STUDS	MW-110	09/28/18	SCD
WA10.01	SIDE & MATE WALL UPLIFT STRAPS	MW-110	09/28/18	SCD
WA12.01	LOWER OF 2 STORY HEADER CHARTS	MW-115	09/28/18	SCD
WA20.01	TYPICAL BAY CONSTRUCTION	MW-120	09/28/18	SCD
WA20.02	TYPICAL BAY CONSTRUCTION		09/28/18	SCD
WA20.03	TYPICAL BAY CONSTRUCTION		09/28/18	SCD
WA20.04	TYPICAL BAY CONSTRUCTION	MW-120	09/28/18	SCD
WA20.05	TYPICAL BAY CONSTRUCTION	MW-120	09/28/18	SCD
Main Win	d Force Resisting System-MWFRS (SW)			
SW01.01	MAIN WIND FORCE RESISTING SYSTEM - GENERAL NOTES		09/28/18	SCD
SW02.01	SHEARWALL PANEL LAYOUT - PRESCRIPTIVE PROCEEDURE		09/28/18	SCD
SW02.02	ROOF DIAPHRAGM / BRACED WALL LINES - PRESCRIPTIVE PROCEEDURES		09/28/18	SCD
SW02.03	BRACED WALL PANELS - PRESCRIPTIVE PROCEEDURES		09/28/18	SCD
SW02.04	BRACED WALL PANELS (CONT.) - PRESCRIPTIVE PROCEEDURES		09/28/18	SCD
SW02.05	BRACED WALL CONNECTIONS - PRESCRIPTIVE PROCEEDURES		09/28/18	SCD
SW03.01	SIMPLIFIED WALL BRACING PROCEEDURE		09/28/18	SCD
SW45.01	ROOF DIAPHRAGM FASTENING	SW-105	09/28/18	SCD
SW45.02	ROOF DIAPHRAGM RANCH (STAPLES & NAILS)	SW-100	09/28/18	SCD
SW50.01	SHEAR WALL FASTENING	SW-105	09/28/18	SCD
SW50.02	RANCH SIDEWALL - STAPLES (140 TO 180 MPH)	SW-110	09/28/18	SCD
SW50.03	RANCH END WALL - STAPLES & NAILS (140 TO 180 MPH)	SW-115	09/28/18	SCD
SW50.04	ENDWALL CHART INTERPOLATION		09/28/18	SCD
SW55.01	HIGH WIND WALL & ROOF CONNECTIONS		09/28/18	SCD
SW55.02	FOUNDATION UPLIFT STRAPS		09/28/18	SCD
SW55.03	HIGH WIND FIELD CONNECTIONS	RF-120	09/28/18	SCD
SW55.04	HIGH WIND PORCH DETAIL	SW-120	09/28/18	SCD
- 4 ()				
Roof (RF)	OFNERAL NOTES. DOOF (SELLING		00/00/40	000
RF01.01	GENERAL NOTES - ROOF / CEILING		09/28/18	SCD
RF02.01	ROOF SYSTEM (TYPICAL)		09/28/18	SCD
RF03.01	ROOF RIDGE BEAM DETAILS ROOF RIDGE BEAM SPAN CHART (2.0e LVL)	DE 100	09/28/18	SCD
RF03.02	ROOF RIDGE BEAM SPAN CHART (2. SAWN LUMBER)	RF-100	09/28/18	SCD
RF03.03 RF04.01	ENDWALL OVERHANG OUTLOOKERS	RF-105 RF-110	09/28/18	SCD
RF04.01	ENDWALL OVERHANG LADDER	RF-110	09/28/18	SCD
RF05.01	TYPICAL CROSS-SECTION (HINGED ROOF TRUSS)	10-110	09/28/18	SCD
RF05.02	HINGED TRUSS & FILLER WEDGE DETAILS	RF-115	09/28/18	SCD
RF05.03	HINGED TRUSS / RIDGE CAP CONNECTION	RF-115	09/28/18	SCD
RF05.04	ROOF VENTILATION REQUIREMENTS	RF-120	09/28/18	SCD
RF06.01	ROOF DORMER	RF-125	09/28/18	SCD
RF06.02	DORMER DETAILS	RF-125	09/28/18	SCD
RF08.01	CAPE TRUSS CONNECTION DETAILS	120	09/28/18	SCD
RF08.02	CAPE TRUSS STAIR FRAMING (ROOF / CEILING)		09/28/18	SCD
RF08.03	CAPE TRUSS DORMER DETAILS (ROOF / CEILING)		09/28/18	SCD
RF08.04	CAPE TRUSS COLLAR TIE CONNECTION	RF-200	09/28/18	SCD
RF08.05	1.5 STORY COLLAR TIE CONNECTION	1255	09/28/18	SCD
	<u> </u>	1		
Exterior (EX)			
EX01.01	PORCH - GENERAL NOTES	ME-100	09/28/18	SCD
EX02.01	RECESSED SIDE PORCH	ME-100	09/28/18	SCD
EX02.02	RECESSED SIDE PORCH	ME-100	09/28/18	SCD
EX03.01	END PORCH & DETAILS	ME-100	09/28/18	SCD

CHAMPION

MANUFACTURED BEAUTIFULLY**

755 W. BIG BEAVER ROAD, SUITE 1000 TROY, MI 48084 PHONE: 248-614-8200



APPROVER'S SEAL



Reviewed: October 8, 2018

Reviewed by:

James A. Rothman, PE

PFS Corporation - QC Dept.

MODIFICATIONS

IRC 2018 DRAWING INDEX

MODEL:

DATE: 09/28/18 SCALE:
DRAWN BY: CORP. CHECKED BY:
BLDG CODE:

CALCS:

FILENAME: 1-INDEX 2018

SHEET NO.:

100.00

PAGE:

PROPRIETARY AND CONFIDENTIAL

THESE DRAWINGS AND SPECIFICATIONS ARE ORIGINAL,
PROPRIETARY AND CONFIDENTIAL MATERIALS OF
CHAMPION HOME BUILDERS, INC.
COPYRIGHT © 2018 BY CHAMPION

GENERAL NOTES: (PER IRC 2018)

- THE ACTUAL FOUNDATION IS DEPENDENT UPON UNIQUE SITE CONDITIONS WHICH REQUIRES DESIGN BY A PROFESSIONAL ENGINEER AND APPROVAL FROM THE LOCAL AUTHORITY HAVING JURISDICTION.
- 2. FOUNDATION DESIGN IS BASED ON AN ASSUMED NON-EXPANSIVE SOIL WITH CAPACITY OF 2000 PSF. SOIL TYPE AND BEARING CAPACITY VARIATION MAY SIGNIFICANTLY ALTER DESIGN REQUIREMENTS. CONSULT LOCAL AHJ OR ENGINEERING PROFESSIONAL FOR ADDITIONAL INFORMATION.
- 3. ALL ASPECTS OF FOUNDATION CONSTRUCTION ARE TO BE PERFORMED ON SITE BY OTHERS, AND IS SUBJECT TO LOCAL BUILDING CODE REQUIREMENTS AND APPROVAL.
- 4. VERIFY ALL DIMENSIONS AND SUPPORT LOCATIONS OF THE HOME PRIOR TO CONSTRUCTION.
- 5. FOOTINGS SHALL BE CENTERED UNDER ALL SUPPORTS ALONG THE MARRIAGE WALL.
- 6. FINISH GRADE TO BE A MINIMUM 8" BELOW TOP OF FOUNDATION WALL.
- 7. MASONRY WEEP HOLES, FLASHING, AND TIE STRAPS ARE SUBJECT TO LOCAL CODE REQUIREMENTS.
- 8. ALL FOUNDATION WALLS LOCATED IN A HIGH WATER TABLE SHALL BE WATERPPROOFED PER IRC REQUIREMENTS. ALL OTHER FOUNDATIONS SHALL BE DAMP PROOFED PER IRC REQUIREMENTS.
- 9. ALL BASEMENTS SHALL HAVE AT LEAST ONE OPERABLE EMERGENCY ESCAPE AND RESCUE OPENING(S) PER IRC R310.
- 10. TYPE "M" OR "S" MORTAR SHALL BE USED IN ALL MASONRY.

CRAWLSPACE:

- 1. PROVIDE CRAWL SPACE VENTILATION EQUAL TO 1/150 OF THE ACTUAL ENCLOSED CRAWL SPACE AREA. (144 SQ. IN. / 150 SQ. FT.)
- 2. PROVIDE POSITIVE UNDER DRAINAGE, SUGGEST MINIMUM 4" PEA GRAVEL WITH 6 MIL POLYETHYLENE VAPOR BARRIER.
- 3. 18"x24" CRAWL SPACE ACCESS TO BE PROVIDED (MINIMUM)
- 4. CRAWL SPACE CLEARANCE TO BE 18" MINIMUM BELOW BOTTOM OF FLOOR JOISTS TO GRADE.
- 5. PROVIDE GFCI RECEPTACLE AND SWITCHED LIGHT FIXTURE AT CRAWLSPACE ACCESS.
- 6. WHERE INTERIOR GROUND LEVEL IS BELOW OUTSIDE GRADE, MEASURES SHALL BE TAKEN TO ASSURE POSITIVE DRAINAGE.
- 7. GROUTED PIERS MAY BE DRY STACKED. UN-GROUTED PIERS MAY BE DRY STACKED AND SURFACE BONDED WITH CEMENT IN ACCORDANCE TO MANUFACTURER'S INSTALLATION INSTRUCTIONS.
- 8. UNBALANCED BACKFILL SHALL NOT EXCEED 4'-0" ON ALL CRAWLSPACES.

BASEMENT:

- 1. EXTERIOR FOOTINGS SHALL EXTEND BELOW THE LOCAL FROST LINE OR SHALL BE PLACED A MINIMUM OF 12" BELOW FINISHED GRADE.
- 1. THE FINISHED GRADE SHALL PROVIDE A MINIMUM SLOPE OF ONE-HALF UNIT VERTICAL IN 12 UNITS HORIZONTAL, FOR A MINIMUM OF 10 FEET FROM THE HOME.
- 2. FOUNDATION INSULATION, WHEN INSTALLED, SHALL BE PERFORMED ON SITE BY OTHERS AS REQUIRED BY LOCAL BUILDING CODES.
- 3. DRAINAGE AND WATERPROOFING AS REQUIRED BY SITE CONDITIONS, SHALL BE INSTALLED ON SITE BY OTHERS PER IRC SPECIFICATIONS.
- 4. THE REINFORCEMENT LOCATED AT TOP OF FOUNDATION WALL FOR ON-FRAME DESIGNS PROVIDES LATERAL RESISTANCE FOR SOIL PRESSURE PER IRC 2018.

TABLE 1 UN-REINFORCED FOOTING SIZE CHART

FOOTING SIZE (IN)	MAX. LOAD (KIPS)
22x22x6	6.72
24x24x8	8.00
26x26x10	9.39
28x28x12	10.8
30x30x14	12.5
32x32x16	14.2
34x34x18	16.0

NOTES:

- CHART BASED ON SOIL CAPACITY OF 2000 PSF. GREATER SOIL CAPACITY MAY SIGNIFICANTLY REDUCE SPREAD FOOTING DIMENSION/ REINFORCEMENT REQUIREMENTS. CONSULT LOCAL AHJ OR ENGINEERING PROFESSIONAL FOR VERIFICATION.
- PIERS OUTSIDE THIS SCOPE MUST BE DESIGNED BY A PROFESSIONAL ENGINEER, PER LOCAL CODES AND SOIL BEARING CAPACITY GIVEN BY LAHJ.

CHAMPION

MANUFACTURED BEAUTIFULLY**

755 W. BIG BEAVER ROAD, SUITE 1000 TROY, MI 48084 PHONE: 248-614-8200



APPROVER'S SEAL



Reviewed: October 8, 2018

Reviewed by:
James A. Rothman, PE
PFS Corporation - QC Dept.

MODIFICATIONS

TITLE:

GENERAL NOTES

MODEL:

DATE: 09/28/18 SCALE:
DRAWN BY: CORP. CHECKED BY:
BLDG CODE: IRC 2018

CALCS:

FILENAME: 8-FOUNDATION SECTION IRC 2018

SHEET NO.

FD01.01

PAGE:

1 OF 1

PROPRIETARY AND CONFIDENTIAL

THESE DRAWINGS AND SPECIFICATIONS ARE ORIGINA PROPRIETARY AND CONFIDENTIAL MATERIALS OF CHAMPION HOME BUILDERS, INC.
COPYRIGHT © 2018 BY CHAMPION

RANCH HIGH SNOW DESIGN SPECIFICATIONS

DESIGN CRITERIA:

GROUND SNOW LOAD: 180 PSF MAX. ROOF DEAD LOAD: OVERHANG LENGTH: WIND SPEED: 18" MAX. 180 MPH $\mathrm{V}_{\mathrm{ULT}}$ MAX. (3 SEC GUST, EXP.C)

- NOTES:
 1. ALL LUMBER SHALL BE SPF#2 UNLESS OTHERWISE NOTED. ALL LVL SHALL BE $F_B = 3,100 \text{ PSI}$, FV = 285 PSI, 2.0 E
- VALUES SHOWN IN TABLES ARE STUD LENGTH ONLY AND
- DO NOT INCLUDE WALL PLATES.
 4. VALUES FOR SPANS ARE CLEAR SPAN.
 5. SEE REFERENCED PAGE OF SYSTEMS MANUAL FOR INFORMATION NOT SHOWN.

		END ZONE	INTERIOR ZONE		
WIND (MPH)	STUD GRADE	STUD SPACING (IN)			
WIND (MPH)	STUD GRADE	16	16		
180	SPF #2	115	124		

2x6 EXTERIOR WALL STUD

RANCH JACK STUD CHART MAXIMUM SIDEWALL OPENING (FT.)

		2x6 SPF#2					
		(ROUND	SNOW LO	DAD (PSF	:)	
	PLY(S)	100	120	140	160	180	
9' SIDEWALLS	1	17	14	12	10	9	
(MAX.)	2	36	29	26	21	19	

RANCH PORCH POST REQUIREMENTS MAXIMUM SPAN (FT.)

	POST HEIGHT 108" MAX
(PSF)	(3) 2x6's
180	8'-0"

*SPANS BASED ON CENTER POST, CORNER POST SPANS MAY BE DOUBLED. (IE: NO CENTER POST IF HEADER WILL SPAN)

POST MATERIAL SHALL BE:
(3) PLY SPF #2 (MIN.), FASTENED TOGETHER WITH PVA GLUE AND $\frac{7}{16}$ x2 $\frac{1}{2}$ "x15 GA. STAPLES @ 12" O.C.

(3) PLY SIDEWALL LUMBER HEADER CHART

			SPECIES			SPF#2						
			HEADER	GROUND SNOW LOAD / ROOF LIVE LOAD (PSF)								
			SIZE	100 / 77	120 / 92.4	140 / 107.8	160 / 123.2	180 / 138.6				
			2x4	41 / 1	38 / 1	36 / 1	34 / 1	32 / 1				
		(MAX)	2x6	60 / 1	56 / 1	53 / 1	50 / 1	48 / 1				
		"	2x8	79 / 1	74 / 1	69 / 2	66 / 2	63 / 2				
		140"	2x10	97 / 2	91 / 2	85 / 2	81 / 2	77 / 2				
			2x12	113 / 2	106 / 2	99 / 2	94 / 2	90 / 2				
DER	_		2x4	39 / 1	36 / 1	34 / 1	32 / 1	31 / 1				
HEA	IDT	160" (MAX)	2x6	57 / 1	53 / 1	50 / 1	47 / 1	45 / 1				
TRIPLE PLY HEADER	-LOOR WIDTH		160" (M	2x8	75 / 1	70 / 2	66 / 2	62 / 2	59 / 2			
딜	8			160	2x10	92 / 2	86 / 2	81 / 2	77 / 2	73 / 2		
TRI	ш		2x12	107 / 2	100 / 2	94 / 2	89 / 2	85 / 2				
			2x4	37 / 1	34 / 1	32 / 1	30 / 1	29 / 1				
		AX)	2x6	54 / 1	50 / 1	47 / 1	45 / 1	43 / 1				
		182" (MAX)	2x8	71 / 2	66 / 2	62 / 2	59 / 2	56 / 2				
		182	2x10	87 / 2	81 / 2	77 / 2	73 / 2	69 / 2				
			2x12	101 / 2	95 / 2	89 / 2	85 / 2	81 / 2				

. $\underline{\text{NOTE:}}$ NUMBER OF JACK STUDS IN CHART IS BASED ON BEARING AREA REQUIREMENTS, NUMBER OF JACK STUDS MAY HAVE TO BE INCREASED BASED ON THE NUMBER OF STRAPS REQUIRED.

(3) PLY SIDEWALL LVL HEADER CHART

			SPECIES		LVL 2.0E (F _B = 3,100 PSI)								
HEADER			HEADER	GR	GROUND SNOW LOAD / ROOF LIVE LOAD (PSF)								
			SIZE	100 / 77	120 / 92.4	140 / 107.8	160 / 123.2	180 / 138.6					
			3½	59 / 1	56 / 1	53 / 1	51 / 1	49 / 1					
		AX)	5½	93 / 2	89 / 2	84 / 2	80 / 2	77 / 2					
		140" (MAX)	71/4	123 / 2	117 / 2	111 / 2	106 / 2	102 / 2					
		140	91/4	157 / 2	149 / 2	142 / 3	136 / 3	130 / 3					
			111/4	181 / 3	181 / 3	173 / 3	165 / 3	159 / 3					
JER.	_		31∕2	57 / 1	54 / 1	51 / 1	49 / 1	47 / 1					
TRIPLE PLY HEADER	FLOOR WIDTH	160" (MAX)	" (MAX)	" (MAX)	5⅓	90 / 2	85 / 2	81 / 2	78 / 2	75 / 2			
PLY	R W				71/4	118 / 2	113 / 2	107 / 2	102 / 2	98 / 2			
PLE	007:		91/4	151 / 2	144 / 3	137 / 3	131 / 3	126 / 3					
TRI	ш		1111/4	181 / 3	175 / 3	167 / 3	159 / 3	153 / 4					
			31/2	55 / 1	52 / 1	50 / 1	47 / 1	46 / 2					
		AX)	5⅓	86 / 2	82 / 2	78 / 2	75 / 2	72 / 2					
		182" (MAX)	71/4	114 / 2	109 / 2	103 / 2	99 / 3	95 / 3					
	182	182	9⅓	146 / 3	139 / 3	132 / 3	126 / 3	121 / 3					
			1111/4	177 / 3	169 / 3	161 / 3	153 / 4	146 / 4					

*NOTE: NUMBER OF JACK STUDS IN CHART IS BASED ON BEARING AREA REQUIREMENTS, NUMBER OF JACK STUDS MAY HAVE TO BE INCREASED BASED ON THE NUMBER OF STRAPS REQUIRED.

LVL RIDGE BEAM CALCULATION

LVI 2 0E (ER = 3 100 PSI)


CDECTEC

SPECIES		LVL 2.0E (FB = 3,100 PSI) GROUND SNOW LOAD / ROOF LIVE LOAD (PSF)								
BEAM SIZE			G	Round Snow	LOAD / ROOF	LIVE LOAD (PS	F)			
	(IN.)		100 / 77	120 / 92.4	140 / 107.8	160 / 123.2	180 / 138.6			
		7-1/4	81 / 3	76 / 3	71 / 3	68 / 3	64 / 3			
		7-7/8	88 / 3	82 / 3	77 / 3	73 / 3	70 / 3			
		8-5/8	95 / 3	89 / 3	84 / 3	80 / 4	76 / 4			
		9-1/4	102 / 3	95 / 3	90 / 4	85 / 4	81 / 4			
	Š.	11-1/4	123 / 4	115 / 4	108 / 4	103 / 5	98 / 5			
	140" (MAX.)	11-7/8	129 / 4	121 / 4	114 / 4	108 / 5	103 / 5			
	140'	14	151 / 5	141 / 5	133 / 5	126 / 5	120 / 6			
		16	171 / 5	160 / 5	151 / 6	143 / 6	136 / 6			
		18	192 / 6	179 / 6	169 / 6	160 / 7	153 / 7			
		20	212 / 6	198 / 7	187 / 7	177 / 7	169 / 8			
		24	252 / 7	235 / 8	222 / 8	210 / 9	200 / 9			
		7-1/4	76 / 3	71 / 3	67 / 3	63 / 3	58 / 3			
		7-7/8	82 / 3	76 / 3	72 / 3	68 / 4	63 / 4			
		8-5/8	89 / 3	83 / 3	79 / 4	74 / 4	69 / 4			
_		9-1/4	95 / 3	89 / 4	84 / 4	84 / 4 80 / 4				
FLOOR WIDTH	Š.	11-1/4	115 / 4	107 / 4	101 / 5	96 / 5	90 / 5			
R ≪	160" (MAX.)	11-7/8	121 / 4	113 / 5	106 / 5	101 / 5	96 / 5			
FLOC	160	14	141 / 5	132 / 5	124 / 5	118 / 6	112 / 6			
		16	160 / 5	150 / 6	141 / 6	134 / 6	128 / 7			
		18	179 / 6	168 / 6	158 / 7	150 / 7	143 / 8			
		20	198 / 7	185 / 7	174 / 7	165 / 8	158 / 8			
		24	235 / 8	220 / 8	207 / 9	197 / 9	187 / 10			
		7-1/4	71 / 3	66 / 3	61 / 3	57 / 3	53 / 3			
		7-7/8	77 / 3	72 / 3	67 / 4	62 / 4	57 / 4			
		8-5/8	84 / 3	78 / 4	73 / 4	68 / 4	63 / 4			
		9-1/4	89 / 4	84 / 4	79 / 4	72 / 4	67 / 4			
	××.	11-1/4	108 / 4	101 / 5	95 / 5	88 / 5	82 / 5			
	182" (MAX.	11-7/8	113 / 4	106 / 5	100 / 5	93 / 5	87 / 5			
	182	14	132 / 5	124 / 6	117 / 6	110 / 6	102 / 6			
		16	150 / 6	140 / 6	132 / 7	126 / 7	117 / 7			
		18	168 / 6	157 / 7	148 / 7	140 / 8	132 / 8			
		20	186 / 7	174 / 8	164 / 8	155 / 8	146 / 9			
		24	221 / 8	206 / 9	194 / 9	184 / 10	176 / 10			

CHAMPION

HOME BUILDERS

755 W. BIG BEAVER ROAD, SUITE 1000 TROY, MI 48084 PHONE: 248-614-8200



APPROVER'S SEAL

MODIFICATIONS

A. UPDATED ALL WIND LOADS TO 180MPH, EXP. C SCD, 11/30/2020

HIGH SNOW SPAN TABLES

MODEL:

SCALE: DATE: 06/15/2020 DRAWN BY: CORP. CHECKED BY: BLDG CODE: IRC 2018 CALCS: HS-100A

FILENAME: 15-SPECIAL SECTION IRC 2018 SHEET NO.:

SP01.01A

PAGE:


1 OF 1

PROPRIETARY AND CONFIDENTIAL

THESE DRAWINGS AND SPECIFICATIONS ARE ORIGINAL PROPRIETARY AND CONFIDENTIAL MATERIALS OF CHAMPION HOME BUILDERS, INC. COPYRIGHT © 2021 BY CHAMPION

GENERAL NOTES:

- 1. THIS FASTENING SCHEDULE TO BE USED FOR ALL COMPONENTS UNLESS NOTED OTHERWISE.
- 2. FASTENING SCHEDULE IS BASED ON SPF LUMBER MINIMUM.
- 3. WHEN GLUE IS SPECIFIED, 80% MINIMUM COVERAGE IS TO BE USED UNLESS SPECIFIED OTHERWISE. GLUE TO CONFORM TO ASTM C557.
- 4. ALL FASTENERS ARE MINIMUM. LARGER FASTENERS AND/OR CLOSER SPACING MAY BE USED PROVIDED THEY DO NOT DAMAGE THE STRUCTURAL MEMBER.
- 5. FASTENER SPACING MAY VARY 25% AS LONG AS THE REQUIRED QUANTITY OVER A GIVEN DISTANCE IS MAINTAINED. EXAMPLE: IF FASTENER SPACING IS CALLED OUT 8" O.C. BUT ACTUAL SPACING IS 10" BETWEEN (2) FASTENERS THAN O.K. IF (4) FASTENERS EFFECTIVE WITHIN 32" SPACING.
- 6. "TOED" FASTENERS TO BE INSTALLED AT A 30° ANGLE WITH THE RECEIVING MEMBER AND START APPROXIMATELY 1/3 THE LENGTH FROM MEMBER END. STAPLES SHALL NOT BE "TOED" (SEE FIGURE A THIS SHEET).
- 7. FOR STAPLES NOT SPECIFIED ON THIS DRAWING SEE APPLICABLE DETAILS IN THIS PACKAGE.



EITHER TOE-NAIL <u>OR</u> TOE-SCREW. (TOE-STAPLING IS NOT ALLOWED)

APPROVER'S SEAL

Reviewed: October 8, 2018

CHAMPION

MANUFACTURED BEAUTIFULLY**

755 W. BIG BEAVER ROAD, SUITE 1000 TROY, MI 48084 PHONE: 248-614-8200

RADO LICEN

ENGINEER'S / ARCHITECTS SEAL

Reviewed by: James A. Rothman, PE PFS Corporation - QC Dept.

MODIFICATIONS

GENERAL NOTES / FASTENER SUBSTITUTION **FASTENING**

MODEL:

DATE: 09/28/18	SCALE:
DRAWN BY: CORP.	CHECKED BY:
BLDG CODE: IRC 2018	
CALCS: FA-100	

FILENAME: FASTENING

SHEET NO .:

FA01.01 1 OF 1 PAGE:

PROPRIETARY AND CONFIDENTIAL

THESE DRAWINGS AND SPECIFICATIONS ARE ORIGINA PROPRIETARY AND CONFIDENTIAL MATERIALS OF CHAMPION HOME BUILDERS, INC. COPYRIGHT © 2018 BY CHAMPION


FASTENER SUBSTITUTION NOTES:

- 1. THE SHOWN SUBSTITUTION CHART IS APPLICABLE TO ALL LUMBER SPECIES.
- 2. FOR TOE-FASTENING DETAILS SEE "FIGURE A" ABOVE, WHERE "L" IS THE LENGTH OF THE FASTENER.
- 3. THE EDGE DISTANCE, END DISTANCE AND FASTENER SPACING SHALL BE SUFFICIENT TO PREVENT THE SPLITTING OF THE WOOD.
- 4. FOR REQUIRED PENETRATION DETAILS SEE "FIGURE B" THIS SHEET.
- 5. DURATION FACTOR = 1.0 FOR ALL LOAD CAPACITIES.
- 6. APPLICABLE CODES NDS 2018 (NAILS & SCREWS) & ESR-1539 (STAPLES)

SUBSTITUTION METHOD (2x MATERIAL ONLY):

- CHART IS ONLY VALID WHERE BOTH THE MEMBERS IN SINGLE SHEAR ARE OF THE SAME SPECIES AND 2" NOMINAL IN THICKNESS.
- MULTIPLY THE NUMBER OF THE FASTENERS SPECIFIED BY THE MULTIPLIER SHOWN IN THE TABLE BELOW IN THE COLUMN UNDER THE FASTENER DESIRED TO OBTAIN THE EQUIVALENT NUMBER OF FASTENERS DESIRED.
- 3. IF THE FASTENER SPACING IS SPECIFIED ON THE APPROVED DRAWING, DIVIDE THE SPACING SPECIFIED BY THE BELOW 'MULTIPLIER' TO OBTAIN THE SUBSTITUTE FASTENER SPACING.

		FASTENER DESIRED															
FASTENER SPECIFIED	15 GA. STAPLE	14 GA. STAPLE	0.099x2 ⅓ " NAIL	0.113×2⅓" NAIL	0.113x2½" NAIL	0.120x3" NAIL	0.120x3 <mark>/</mark> 4" NAIL	0.131x2½" NAIL	0.131x3" NAIL	0.131x3 <mark>1⁄</mark> 4" NAIL	0.135x3½" NAIL	0.148x3" NAIL	0.148x3 <mark>/</mark> 4" NAIL	0.162x3½" NAIL	#8 SCREW	#10 SCREW	#12 SCREW
15 GA. STAPLE	1.0	0.9	1.2	0.9	0.8	0.6	0.6	0.7	0.5	0.5	0.5	0.4	0.4	0.4	0.5	0.4	0.4
14 GA. STAPLE	1.1	1.0	1.3	1.0	0.9	0.7	0.7	0.8	0.6	0.6	0.5	0.5	0.5	0.4	0.6	0.5	0.4
0.099x2 ¼ " NAIL	0.8	0.8	1.0	0.8	0.7	0.5	0.5	0.6	0.4	0.4	0.4	0.4	0.4	0.3	0.5	04	0.3
0.113x2 ¼ " NAIL	1.1	1.0	1.3	1.0	0.9	0.7	0.7	0.8	0.6	0.6	0.5	0.5	0.5	0.4	0.6	0.5	0.4
0.113x2½" NAIL	1.3	1.1	1.5	1.1	1.0	0.8	0.8	0.9	0.7	0.7	0.6	0.5	0.5	0.5	0.7	0.6	0.5
0.120x3" NAIL	1.6	1.5	1.9	1.5	1.3	1.0	1.0	1.1	0.8	0.8	0.8	0.7	0.7	0.6	0.9	0.7	0.6
0.120x3 <mark>¼</mark> " NAIL	1.6	1.5	1.9	1.5	1.3	1.0	1.0	1.1	0.8	0.8	0.8	0.7	0.7	0.6	0.9	0.7	0.6
0.131x2 ½ " NAIL	1.5	1.3	1.8	1.3	10.2	0.9	0.9	1.0	0.8	0.8	0.8	0.6	0.6	0.6	0.8	0.6	0.6
0.131x3" NAIL	1.9	1.7	2.3	1.7	1.5	1.2	1.2	1.3	1.0	1.0	0.7	0.8	0.8	0.7	1.0	0.8	0.8
0.131x3 <mark>¼</mark> " NAIL	1.9	1.7	2.3	1.7	1.5	1.2	1.2	1.3	1.0	1.0	0.9	0.8	0.8	0.7	1.0	0.8	0.8
0.135x3½" NAIL	2.1	1.9	2.5	1.9	1.6	1.3	1.3	1.4	1.1	1.1	0 . 9	0.9	0.9	0.8	1.1	0.9	0.8
0.148x3" NAIL	2.3	2.1	2.8	2.1	1.8	1.4	1.4	1.6	1.2	1.2	1.1	1.0	1.0	0.9	1.3	1.0	0.9
0.148x3 <mark>¼</mark> " NAIL	2.3	2,1	2.8	2.1	1.8	1.4	1.4	1.6	1.2	1.2	1.1	1.0	1.0	0.9	1.3	1.0	0.9
0.162x3½" NAIL	2.6	2.3	3.1	2.3	2.0	1.6	1.6	1.8	1.3	1.3	1.3	1.1	1,1	1.0	1.4	1.1	1.0
#8 SCREW		1.0 0.8 0.7									0.7						
#10 SCREW		DO NOT SUBSTITUTE STAPLES OR NAILS FOR SCREWS UNLESS IT IS SPECIFIED ON THE APPROVED DRAWING 1.0 1.0 0.9															
#12 SCREW															1.4	1.1	1.0



NAIL PENETRATION DETAIL



Project 05-865-HERBERT

Energy Code: 2015 IECC

Location: Yampa, Colorado
Construction Type: Single-family
Project Type: New Construction

Conditioned Floor Area: **3,712 ft2** Glazing Area **13%**

Climate Zone: **7 (9316 HDD)**

Permit Date: Permit Number:

Construction Site: 18195 Hwy 131 Yampa, CO 80483 Owner/Agent: Designer/Contractor:

Compliance: Passes using UA trade-off

Compliance: **0.4% Better Than Code** Maximum UA: **225** Your UA: **226**

The % Better or Worse Than Code Index reflects how close to compliance the house is based on code trade-off rules.

It DOES NOT provide an estimate of energy use or cost relative to a minimum-code home.

NOTE: Slab-on-grade tradeoffs are no longer considered in the UA or performance compliance path in REScheck. Each slab-on-grade assembly in the specified climate zone must meet the minimum energy code insulation R-value and depth requirements.

Envelope Assemblies

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Prop. U-Factor	Req. U-Factor	Prop. UA	Req. UA
Ceiling 1: Flat Ceiling or Scissor Truss	1,856	50.0	0.0	0.026	0.026	48	48
Wall 1: Wood Frame, 16" o.c.	1,488	21.0	0.0	0.057	0.045	70	56
Window 1: Vinyl/Fiberglass Frame:Double Pane with Low-E	171			0.250	0.320	43	55
Door 1: Solid	43			0.290	0.320	12	14
Door 2: Glass	40			0.320	0.320	13	13
Rim Joist: Wood Frame, 16" o.c.	186	21.0	0.0	0.057	0.045	11	8
Crawl 1: Solid Concrete or Masonry Wall height: 4.0' Depth below grade: 3.0' Insulation depth: 4.0'	744	0.0	18.0	0.048	0.055	27	31

Compliance Statement: The proposed building design described here is consistent with the building plans, specifications, and other calculations submitted with the permit application. The proposed building has been designed to meet the 2015 IECC requirements in REScheck Version 4.7.2 and to comply with the mandatory requirements listed in the REScheck Inspection Checklist.

Shaun Penne	Shaun Penne	9/14/2023
Name - Title	Signature	Date

Project Title: 05-865-HERBERT Report date: 09/14/23

Data filename: M:\Eng\PRODUCT LINES\MODELS-SPECIAL\2023\07-JUL\05-865 MOD-PREMIUM LIVING-

HERBERT\APPROVALS\05-865-HERBERT_CO ResCheck.rck



Insulation Rating	R-Value
Above-Grade Wall	21.00
Below-Grade Wall	18.00
Floor	0.00
Ceiling / Roof	50.00
Ductwork (unconditioned spaces):	R-8 (Return Air Grill)

Glass & Door Rating	U-Factor	SHGC
Window	0.25	
Door	0.29	

Heating & Cooling Equipment		Efficiency
Heating System:_	E2EB015H	100
Cooling System:		
Water Heater:	40 Electric - E40-2 RH95	<u>0.9</u> 5

Name: Shaun Penne Date: 9/11/2023

Comments