



# **REVIEWED FOR** CODE COMPLIANCE 04/24/2024



FOUNDATION WALL DETAIL







**EXTERIOR PIER DETAIL** 

#### –EXTENT OF HEADER WITH DOUBLE PORTAL FRAMES (TWO BRACED WALL PANELS) $-\!-\!-$ EXTENT OF HEADER WITH SINGLE PORTAL FRAME (ONE BRACED WALL PANEL) 2'-18' FINISHED WIDTH OF OPENING FOR SINGLE OR DOUBLE PORTAL HEADER TO JACK-STUD STRAP PONY WALL PER WIND DESIGN, MIN 1000 LBF, ON BOTH SIDES OF OPENING OPPOSITE SIDE OF SHEATHING. MIN. 3"x11-1/4" NET HEADER (SEE PLAN) STEEL HEADER PROHIBITED. FASTEN TOP PLATE FASTEN SHEATHING TO HEADER WITH 8d TO HEADER WITH COMMON OR GALVANIZED BOX NAILS IN 3" - TWO ROWS OF 16d GRID PATTERN AS SHOWN. SINKER NAILS AT IF NEEDED, PANEL SPLICE EDGES SHALL OCCUR OVER 3" O.C. TYP. HEADER TO JACK-STUD STRAP PER WIND AND BE NAILED TO COMMON DESIGN, MIN 1000 LBF, ON BOTH SIDES -BLOCKING WITHIN MIDDLE 24" OF OPENING OPPOSITE SIDE OF SHEATHING. OF PORTAL HEIGHT. ONE ROW OF 3" O.C. NAILING IS MIN. DOUBLE 2x4 FRAMING COVERED WITH 7/16" REQUIRED IN EACH PANEL THICK WOOD STRUCTURAL PANEL SHEATHING WITH 8d COMMON OR GALVANIZED BOX NAILS AT 7/16" WOOD STRUCTURAL 3" O.C. IN ALL FRAMING (STUDS, BLOCKING, AND TYPICAL PORTAL FRAME \_ SILLS) TYP. PANEL SHEATHING. CONSTRUCTION MIN. (2) JACK STUDS AND MIN. (2) 3500 LB. STRAP-TYPE HOLD-DOWNS (1) KING STUD, U.N.O. (EMBEDDED INTO CONCRETE AND NAILED INTO FRAMING). (SEE PLAN) FOUNDATION REINFORCEMENT, TYP. MIN. 1000 LB HOLD-DOWN DEVICE (EMBEDDED INTO CONCRETE AND NAILED INTO FRAMING). (SEE PLAN) MIN. (1)5/8"ø OR (2)1/2"ø ANCHOR BOLT INSTALLED PER R403.1.6 - WITH 2"x2"x3/16" PLATE WASHER

APA PORTAL FRAME DETAIL

# GENERAL NOTES

All work shall conform to the requirements of the most recent codes and adopted amendments by local authorities. Codes included, but not limited to, are: the International Building Code (IBC): the International Residential Code (IRC); Portions of the American Concrete Institute (ACI) ACI301, ACI318 and ACI332R; the American Institute of Steel Construction (AISC) Manual of Steel Construction; the American Forest and Paper Association/American Wood Council National Design Specifications (NDS); and the American Welding

If shear wall information is not shown, walls are to be constructed per the braced wall section of the IRC. Code revision in use: IRC 2021 Notify engineer immediately if a different revision is in use.

#### **SOILS** Report By: Western Slope Geotech, Inc. #22-1036

Spread Footing Recommendations

<u>Upper Soils</u> <u>Lower Soils</u> Max. 2500 psf Max. N/A psf

Min. N/R psf Min. N/A psf

**Drilled Pier Recommendations** Max. End Bearing Capacity N/A ksf Side Shear N/A psf Minimum total length N/A ft

Equivalent Fluid Density 40 pcf (active)

It is the contractors responsibility to read and understand all portions of the referenced soil report. Contact the geotechnical engineer, prior to construction, with questions regarding the soil report.

An open hole observation is required and shall be performed by, or under the direct supervision of, a qualified geotechnical engineer. It is the contractor/owners responsibility to contact the geotechnical engineer, a minimum of 24 hours in advance, to schedule the open hole observation. Soil conditions which are inconsistent with the soil report may require additional evaluation or a foundation re-design. The owner/contractor is responsible for reporting any inconsistencies to the foundation engineer. All foundation elements shall bear a minimum of 48" below grade, or per local code, and shall bear upon undisturbed, native soils or on structural fill acceptable to the geotechnical engineer and compacted per specifications set forth by approved testing methods. The bottom of foundations shall be placed at least 2 feet above the maximum seasonal groundwater level unless noted otherwise by the geotechnical engineer. Footing and foundation wall forms and reinforcement will be observed upon the contractor/owners request, prior to the placement of concrete. All construction observations are an additional cost.

### <u>LOADS</u>

Live Load = 95 psf Dead Load = 15 psf Live Load = 40 psf Dead Load = 10 psf Ground Snow Load = 124 psf Snow: Ultimate Wind Speed (Vult) = 115 mph, Exposure C

### MATERIALS

Seismic:

Zone C

Concrete: All concrete shall use Type II cement, an air content of 6% + /- 1%, and a minimum 28-daystrength (f'c) of 3000 psi., unless otherwise specified. Concrete shall be proportioned, placed and cured in accordance with all applicable sections of the current ACI codes. Concrete Reinforcement: Shall be deformed Grade 60, or better with the exception of #3 ties or stirrups

which could be Grade 40. All reinforcing steel shall conform to ASTM A615. Reinforcement shall not be welded; where welding is specified, the steel shall conform to ASTM A706. Minimum concrete cover over reinforcing steel cast against and permanently exposed to earth is 3 inches. Minimum concrete cover over reinforcing steel exposed to earth or weather is  $1\frac{1}{2}$  inches. Anchor Bolts: Shall be Grade 36 J-type bolt with a minimum  $\frac{1}{2}$ " diameter, with 1" diameter washer

(unless otherwise noted), and a minimum embedment into concrete or masonry of 7 inches. Projections above the concrete shall be such that a washer and nut can be placed and tightened over the sill plate. There shall be a minimum of 2 bolts per sill plate section with one bolt located not more than 12 inches from the end of a plate section or corner and spaced no more than 48" apart. Additional anchor bolt details shall be in accordance with the drawing.

Structural Steel: Structural steel plates, angles, channels, wide flange and miscellaneous shapes shall conform to ASTM A36. Square and rectangular tube shapes shall conform to ASTM A500, Grade B. Standard and Adjustable steel pipe columns shall conform to ASTM A53, Grade B, Schedule 40. Pipe columns shall be 3" or 3½" nominal diameter, unless noted otherwise (U.N.O). Adjustable pipe columns shall have the threads exposed; 1" minimum and 3" maximum. Wood Products: Dimensional lumber shall be Hem Fir #2 or better unless noted otherwise on this plan.

Laminated Veneer Lumber shall have a minimum allowable flexural stress (Fb) of 2,600 psi and a minimum modulus of elasticity (E) of 1,900,000 psi. Glue Laminated Lumber shall have a minimum allowable flexural stress (Fb) of 2,400 psi and a minimum modulus of elasticity (E) of 1,500,000 psi. stallation: Minimum beam bearing at wood framed walls or concrete walls shall be the full beam width by 3 inches unless noted otherwise on the plans. Minimum beam bearings shall be in accordance with applicable codes and/or manufacturer's recommendations. Lumber in contact with concrete or earth shall be pressure treated or foundation grade redwood. Install LVL beams in the longest practical lengths available, lap beams as needed per the manufacturer's specifications. Do not notch or bore beams, columns, joists, rafters or trusses unless shown on the drawings or approved in writing by the engineer. All bolts used in wood framing shall be installed with steel washers. Floor sheathing connections per the

# SLABS-ON-GRADE

A slab on grade, if shown on this plan or in the details, shall not be mistaken as a recommendation to construct a slab on grade for this project. Slabs on grade, placed upon expansive soils, are not recommended for habitable spaces. Soils that are expansive may cause vertical slab movement resulting in damage to structural and/or non—structural items. Alternate methods of floor construction, and the potential risks, should be discussed between the contractor/owner and the geotechnical engineer. If slabs on grade are constructed, appropriate precautions shall be taken to minimize the risk of damage caused by slab movement. Slabs shall be free floating and isolated from grade beams, columns, plumbing or other support structures by use of a ½" isolation strip, minimum. All partition walls on slabs shall have a minimum 2" void space to allow for some vertical slab movement. The void space could be eliminated for suspended (structural) concrete slabs. Any areas with slab on grade construction, placed over expansive soils, should not be finished for a minimum of 3 years after substantial completion. Exterior slabs should not be doweled to the foundation when placed over expansive soils. Slabs on grade are not structural and are not designed unless otherwise noted.

The engineer does not have control or knowledge of specific site grading or backfill procedures. The engineer has not performed a lateral load analysis of foundation walls and will not be responsible for damage caused by earth and hydraulic pressures or improper backfill procedures. It is recommended that the first floor system be installed prior to backfilling to help support the foundation wall. The backfill shall be compacted and graded per the above referenced soils report. At minimum, the slope shall meet the requirements of the governing building code. Backfill may settle over time and should be maintained to ensure positive drainage away from the foundation walls.

The dimensions shown on this plan are from building plans submitted to the engineer and shall be verified by the contractor/owner prior to construction. The contractor/owner shall carefully study and compare all dimensions and elevations indicated on this plan with the contract documents. The engineer shall be notified immediately of any discrepancy between the drawings, or in the layout; of any error, inconsistency, or omission he may discover. The engineer shall not be liable to the contractor/owner for any damages resulting from such errors, inconsistencies, or omissions in the contract documents nor shall the contractor/owner take advantage of any error or omission in the drawings or the contract documents. Architectural portion of the plan is by the owner. Owner/contractor shall verify that this drawing conforms to the final architectural version. The contractor is responsible for the location of all utilities on the site, both horizontally and vertically. All superstructure framing is to be constructed in accordance with the current International Residential Code requirements for Braced Wall Framing (Chapter 6, IRC) unless otherwise noted. Lateral Load Resisting Elements that are not in accordance with the Braced Wall Framing standards and Moment Frames designed by the Engineer are shown on the drawings in Tabular form or construction details. The above reference to the seismic loading are for informational purposes only. Calculations are performed with assumed truss bearing conditions. A final truss design shall be provided to and reviewed by CDS Engineering Corporation prior to construction. Any load carrying member not shown on this plan or any other framing requirements not shown on this plan shall be the responsibility of the contractor/owner. All framing and connections shall be in accordance with the conventional construction requirements of the IBC, IRC, applicable regulatory agencies, and adopted standards. Brick ledges, foundation steps, insets, beam pockets, basement windows, etc. may not be shown. Any crawl space or structural floor cavity shown on this plan does not include provisions for the control of mold growth or moisture levels. Environmental control provisions for these or other applicable areas is the responsibility of the contractor/owner. These plans and all associated work performed by CDS Engineering Corporation (ENGINEER) shall remain the property of the ENGINEER and may not be used by any other entity for any other endeavor without the written consent of the ENGINEER.

Kevin F. Becker, Kevin F. Becker, P.E. P.E.

2024.04.03 08:12:42-06'00'



Engineering Corporation

165 2nd St. S.W., Loveland, Colorado 80537 Tele: (970) 667-8010

"Consulting Engineers and Professional Construction Managers"

CIVIL / STRUCTURAL ENGINEERING, GEOTECHNICAL AND FOUNDATION ENGINEERS, LAND AND MUNICIPAL PLANNING, LAND AND CONSTRUCTION SURVEYS / SOILS / CONCRETE / ASPHALT

TESTING AND FIELD INSPECTION



04/03/2024 For and on behalf of

CDS Engineering, Corp.


APP.	KFB	XFB				
≻	TSS	TSS	-	-	-	
DATE   BY  APP.	03/21/24 TSS KFB	04/03/24 TSS	//	//	//	//
RECORD OF ISSUE	INITIAL ISSUE	REVISED PR COUNTY COMMENTS				
	<b>⊢</b> :	2	33	4	5.	9

KFB TSS DRAWN BY CHECKED BY DATE ISSUED | 03/21/2024 SCALE N.T.S.

MODEL NO.

SHEET 1 OF 4 TOTAL SHEET

24-2324



**REVIEWED FOR** CODE COMPLIANCE 04/24/2024

Engineering Corporation

165 2nd St. S.W., Loveland, Colorado 80537 Tele: (970) 667-8010

"Consulting Engineers and Professional Construction Managers"

CIVIL / STRUCTURAL
ENGINEERING, GEOTECHNICAL AND
FOUNDATION ENGINEERS, LAND
AND MUNICIPAL PLANNING, LAND AND CONSTRUCTION SURVEYS /
SOILS / CONCRETE / ASPHALT
TESTING AND FIELD INSPECTION



For and on behalf of CDS Engineering, Corp.

- 7 % 4 G 0

**OUNDATION PL** 

3 - #4 REBAR

4 - #4 REBAR

5 - #4 REBAR

6 - #4 REBAR

7 - #4 REBAR


8 - #4 REBAR

DESIGNED BY DRAWN BY CHECKED BY

DATE ISSUED 03/21/2024 SCALE 1/4"=1'-0"MODEL NO.

PROJECT NO. 24-2324

SHEET 2 OF 4 TOTAL SHEET



Engineering

Corporation

165 2nd St. S.W., Loveland, Colorado 80537 Tele: (970) 667-8010

"Consulting Engineers and Professional Construction Managers"

CIVIL / STRUCTURAL
ENGINEERING, GEOTECHNICAL AND
FOUNDATION ENGINEERS, LAND
AND MUNICIPAL PLANNING, LAND AND CONSTRUCTION SURVEYS / SOILS / CONCRETE / ASPHALT
TESTING AND FIELD INSPECTION



For and on behalf of CDS Engineering, Corp.

- 4 6 4 6 a


UPPER FLOOR AND OWER ROOF FRAMING

DRAWN BY

CHECKED BY DATE ISSUED 03/21/2024 SCALE 1/4"=1'-0"MODEL NO.

24-2324

SHEET 3 OF 4 TOTAL SHEET



8d COMMON

CONNECTOR

8d COMMON

-- ALL PANEL EDGES ARE TO BE BLOCKED

14, 15, OR 16 GAUGE 1½" MIN. LENGTH

**REVIEWED FOR** CODE COMPLIANCE 12/05/2024

Engineering Corporation 165 2nd St. S.W., Loveland, Colorado 80537 Tele: (970) 667-8010 "Consulting Engineers and Professional Construction Managers"

> AND CONSTRUCTION SURVEYS /
> SOILS / CONCRETE / ASPHALT
> TESTING AND FIELD INSPECTION For and on behalf of CDS Engineering, Corp.

> > - 7 % 4 G

CIVIL / STRUCTURAL ENGINEERING, GEOTECHNICAL AND FOUNDATION ENGINEERS, LAND AND MUNICIPAL PLANNING, LAND

FRAMIN

DESIGNED BY |

2x TRIMMERS 2x KINGS

DRAWN BY CHECKED BY DATE ISSUED 03/21/2024 SCALE 1/4"=1'-0"MODEL NO.

PROJECT NO.

SHEET 4 OF 4 TOTAL SHEET

24-2324