

INSTALLATION NOTES

Record Set Stamp

05/10/2022

PARTS FOR PO PURCHASE (NOT OCCURRING IN GREAT PLAINS)

QTY	MANUFACTURERS PART NUMBER AND DESCRIPTION
*	*
*	*
*	*
*	*
*	*

AHJ SPECIFICS:	DESIGNER NOTES:	INSTALLATION SPECIFICS:
Snow load: 85 psf Wind speed: 115 mph High Temp: N/A Low Temp: N/A Max Number of Modules per MCI: 10	<u>Telsa Inverter DC Stringing Rules</u> <ul style="list-style-type: none"><li>Min string length = 6</li><li>Max string length = 37</li><li>Avoid stringing PV arrays in series between mounting planes if possible; if needed only string within the same pitch &amp; azimuth (+/- 3 degrees)</li><li>Minimum module per MP or sub-array = 6</li><li>Only string between stories if needed to meet sold system size</li><li>Default to larger string sizes to minimize number of strings</li><li>Avoid hard shading</li></ul> <u>Tesla MCI Rules</u> <ul style="list-style-type: none"><li>(1) MCI between sub-strings if string spans between mounting planes or between stories</li><li>(1) MCI at the start or end of a string</li><li>(5) MCIs maximum allowed per string</li><li>(1) MCI maximum per 10 Solar Roof modules in each string</li></ul>	Solar Roof Area (sqft):3622  Alternative Roofing (not included in the BOM): NA  PV System Size: 13.752  Red Flags: None  Note: Valley tile reinforcement required.    Total array perimeter is 1883' if pest abatement is required Material Hoist Required
		<u>SAFETY CONCERNS:</u>
		N/A

	JOB NUMBER: JB-8042552 00	CUSTOMER: Kevin Daly 35040 Country Green Ln Steamboat Springs, CO 80487  303-808-5445	DESCRIPTION: 13.752 KW PV ARRAY   PAGE NAME: INSTALLATION NOTES	DESIGN:	SHEET: SC 1 REV: DATE: 4/26/2022	
	MOUNTING SYSTEM: TESLA SOLAR ROOF					
	MODULES: (191) TESLA SR72T2; 72 W, 65.40 W PTC					
	INVERTER: Multiple Inverters					

## SAFETY PLAN

INSTRUCTIONS:

1. USE SYMBOLS IN KEY TO MARK UP JCO SHEET.
2. SAFETY PLANS MUST BE MARKED BEFORE JOB STARTS AS PART OF THE PRE-PLAN.
3. DOCUMENT ALL ADDITIONAL HAZARDS ON THIS PAGE & MAKE NOTES ON THE JCO SHEET

IN CASE OF EMERGENCY:

NEAREST HOSPITAL OR OCCUPATIONAL/INDUSTRIAL CLINIC  
NAME \_\_\_\_\_

ADDRESS\_\_\_\_\_

SAFETY COACH CONTACT INFORMATION

NAME \_\_\_\_\_

PHONE\_\_\_\_\_

ALL EMPLOYEES ON SITE SHALL BE MADE AWARE OF THE SAFETY PLAN AND SIGN INDICATING THAT THEY ARE AWARE OF THE HAZARDS ON-SITE AND THE PLAN FOR WORKING SAFELY.

NAME \_\_\_\_\_ SIGNATURE \_\_\_\_\_

---

FALL COMPETENT

ELECTRICAL QUALIFIED

---

---

---

---



---

---

















DATE: \_\_\_\_\_ TIME: \_\_\_\_\_

### SELECT ELECTRICAL TIE IN METHOD

MAIN / SUB	BREAKER/TAP
1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10
11	11
12	12
13	13
14	14
15	15
16	16
17	17
18	18
19	19
20	20
21	21
22	22
23	23
24	24
25	25
26	26
27	27
28	28
29	29
30	30
31	31
32	32
33	33
34	34
35	35
36	36
37	37
38	38
39	39
40	40
41	41
42	42
43	43
44	44
45	45
46	46
47	47
48	48
49	49
50	50
51	51
52	52
53	53
54	54
55	55
56	56
57	57
58	58
59	59
60	60
61	61
62	62
63	63
64	64
65	65
66	66
67	67
68	68
69	69
70	70
71	71
72	72
73	73
74	74
75	75
76	76
77	77
78	78
79	79
80	80
81	81
82	82
83	83
84	84
85	85
86	86
87	87
88	88
89	89
90	90
91	91
92	92
93	93
94	94
95	95
96	96
97	97
98	98
99	99
100	100



### MARK UP KEY

-  PERMANENT ANCHOR
-  TEMPORARY ANCHOR
-  DELINEATOR FOR WARNING LINE  
(LOW-SLOPE ROOF ONLY)
-  GUARD RAIL STANCHION  
(LOW-SLOPE ROOF ONLY)
-  INSTALLER LADDER
-  AUDITOR LADDER
-  JUNCTION/COMBINER BOX
-  STUBOUT
-  SKYLIGHT
-  NO LADDER ACCESS (STEEP GRADE OR  
GROUND LEVEL OBSTRUCTIONS)
-  RESTRICTED AREA  
(TESLA EMPLOYEES ONLY)
-  CONDUIT
-  GAS SHUTOFF
-  WATER SHUTOFF
-  SERVICE DROP
-  POWER LINES

MP1	PITCH: 45° (12:12) ARRAY PITCH: 45° (12:12) AZIMUTH: 174 ARRAY AZIMUTH: 174 MATERIAL: Solar Roof STORY: Two
-----	---

**Record Set Stamp**

05/10/2022

JOB NUMBER: JB-8042552 00

MOUNTING SYSTEM:  
TESLA SOLAR ROOF

MODULES:  
(191) TESLA SR72T2; 72 W, 65.40 W PTC

INVERTER:  
Multiple Inverters

CUSTOMER:  
Kevin Daly  
35040 Country Green Ln  
Steamboat Springs, CO 80487

303-808-5445

DESCRIPTION:  
13.752 KW PV ARRAY

PAGE NAME:  
SAFETY & HOUSING PLAN

DESIGN:	
---------	--

SHEET: SC 2      REV:      DATE: 4/26/2022

This is a worksheet for on-site use as needed. All information **must** be transferred/uploaded through the digital app for all jobs (including the 2 cell phone pics).

ELECTRICAL TESTING					JOB PHOTOS					
Irradiance reading must be taken in the plane of array and at the same time as the I <sub>MP</sub> and P <sub>AC</sub> measurements.					<div>Record Set Stamp</div> <div>Take these photos with your phone. 05/10/2022</div>					
INVERTER #1: SERIAL NUM:					<div><input type="checkbox"/> Finished array photo (pullback)?</div> <div><input type="checkbox"/> String Diagram / Safety Plan?</div> <div><input type="checkbox"/> All inverter or meter labels.</div> <div><input type="checkbox"/> Picture of main disconnect in off position.</div> <div><input type="checkbox"/> Worker in electrical PPE testing the system or completing tie-in.</div> <div><input type="checkbox"/> All ladders set up.</div> <div><input type="checkbox"/> System used to raise modules to roof.</div> <div><input type="checkbox"/> Fall arrester or restraint with employees while in use.</div> <div><input type="checkbox"/> A hazard encountered that isn't noted in the SolarWorks case notes or mentioned in the project preplan.</div> <div><input type="checkbox"/> Unflashed, installed anchor.</div> <div><input type="checkbox"/> Flashed anchor.</div> <div><input type="checkbox"/> In process penetration.</div> <div><input type="checkbox"/> Combo / J box location / Wiring.</div> <div><input type="checkbox"/> Array wire management / grounding.</div> <div><input type="checkbox"/> Rafter upgrades.</div> <div><input type="checkbox"/> All electrical equipment wiring / grounding.</div> <div><input type="checkbox"/> All electrical equipment locations / working clearance.</div> <div><input type="checkbox"/> All conduit, including stubout.</div> <div>Explain if any photos are missing:</div>					
STRING:							1	2	3	4
V <sub>OC</sub>										
I <sub>MP</sub>										
IRRADIANCE										
Power (W) P <sub>AC</sub> :										
INVERTER #2: SERIAL NUM:										
STRING:							1	2	3	4
V <sub>OC</sub>										
I <sub>MP</sub>										
IRRADIANCE										
Power (W) P <sub>AC</sub> :										
INVERTER #3: SERIAL NUM:										
STRING:							1	2	3	4
V <sub>OC</sub>										
I <sub>MP</sub>										
IRRADIANCE										
Power (W) P <sub>AC</sub> :										

JOB INFO			
Did you walk customer through system operation?	Y / N	What and where is the grounding means?	Y / N
Does customer have the gateway connected?	Y / N		
Is grounding mechanism accessible for inspection?	Y / N		
Was placard installed?	Y / N		
Which ladders are required for roof access?	12 24 36		
Are there internal conduit runs?	Y / N		
Are there locked gates that need to be accessed?	Y / N		
Did we tie into an existing subpanel?	Y / N		
Does as-built match approved drawings?	Y / N	Are there punch list items remaining?	Y / N

	JOB NUMBER:	JB-8042552 00	CUSTOMER: Kevin Daly 35040 Country Green Ln Steamboat Springs, CO 80487	DESCRIPTION: 13.752 KW PV ARRAY	DESIGN:		
	MOUNTING SYSTEM:	TESLA SOLAR ROOF					
	MODULES:	(191) TESLA SR72T2; 72 W, 65.40 W PTC					
	INVERTER:	Multiple Inverters					
			303-808-5445	PAGE NAME: JCO SHEET	SHEET: SC 3	REV: 4/26/2022	DATE:

JOB HAZARD ANALYSIS

Crew leader to fill out all sections below, hold a pre-job safety meeting with all personnel, and upload this completed document and the Safety Plan to the JCO.

Ladder Access

- Ladders must be non-conductive, inspected before each use.
- Extension ladders must be set up on a firm and level surface at a 4-to-1 rise-to-run angle (or 75 degrees) and the top must be secured to the structure. Extension style ladders placed on uneven, lose or slippery surfaces must additionally have the base firmly anchored or lashed so the base will not slip out.
- Extension ladders must be used with walk-through devices or the ladder must extend 36” above the stepping off point.
- A-frame ladders must only be climbed with the ladder spreader bars locked in the open position; A-frame ladders shall not be climbed while in the closed position (ex, closed and used while leaned against a structure).

- Additional Notes:

Mobile Equipment

- Only Qualified operators will operate equipment; operators must maintain a certification on their person for the equipment being operated.
- Type(s) of mobile equipment (type/make/model):
- Qualified operator(s):

Material Handling and Storage

- Materials will be staged/stored in a way that does not present a hazard to client, personnel or public. Materials stored on the roof will be physically protected from falling or sliding off.

Fall Protection

- A Site-specific plan for fall prevention and protection is required prior to starting work and must remain onsite at all times until work is complete; a fall rescue plan must be outlined and discussed among the crew prior to work start.
- The Competent Person is required to be onsite at all times while work at heights is ongoing.
- First-Person-Up (FPU) must install their anchor and connect before any other task, including installing other anchors. The Last-Person-Down (LPD) must be the only person on a roof uninstalling fall protection.

- FPCP (name and title):
- FPU and LPD (name and title):

Electrical Safety

- The Electrical Qualified Person (EQP) is required onsite to perform electrical work.
- All electrical work will be performed with equipment in an electrically safe condition (de-energized) unless approval has been granted prior to work start.
- Service drops and overhead electrical hazards will be identified and protected from contact, as necessary.
- EQP (name and title):

Public Protection

- The safety of the Client and the Public must be maintained at all times.
- The Client and the Public shall be prevented from entering the work zone through the use of barriers and/or signage, as required.
- Company, Client and Public property shall be protected from falling objects.
- Pets (including dogs) shall be secured by their owners prior to work start.
- The client should not leave pets, family members, or others in charge or care of Employees, Contractors, or Temporary Workers.

- Crew leader responsible for communication with the client:
- Pets barricaded away from work areas (N/A, Yes, No):
- Client and public is excluded from work area by barricades (N/A, Yes, No):

Training And Pre-Job Safety Briefing

- All employees onsite shall be made aware of the specific hazards of this project and review this JHA during a pre-job briefing, and their signature indicates awareness of site conditions and the plan to eliminate any hazards identified prior to and during the project.

- Crew Leader (name/title):
- Crew Member (name/title):
- Crew Member (name/title):
- Crew Member (name/title):
- Crew Member (name/title):
- Crew Member (name/title):

Airborne Contaminants:

- Asbestos-containing (Transite) piping (ACP) - Do not disturb (move, drill, cut, fracture, etc.)
- Asbestos-containing exterior building siding (ACS) - Only Asbestos Class III trained personnel can drill or cut into ACS material, and only for purposes of mounting BOS equipment; a completed Asbestos Work Permit is required onsite at all times prior to working with ACS.
- Asbestos-containing thermal insulation (ACI) and Asbestos-containing duct wrapping (ACW) - do not disturb; no attic or crawlspace access is allowed if work to be performed could cause exposure to personnel, client or public.

- Is work around ABC or ABC containing materials being conducted (N/A, Yes, No):
- If yes, list specific tasks and protection in place:

Weather and Environment

- The site supervisor shall forecast the weather conditions at the job site, prior to crew arrival, in order to mitigate any hazards associated with inclement weather (heat, cold, wind, rain, etc.).
- The site supervisor will utilize a portable wind meter (anemometer) to verify actual onsite wind conditions, by checking speed at the ground and on any elevated work surface (ex, rooftop) prior to work start, at midday and prior to solar panel staging on a roof.
- Elevated work involving the moving or maneuvering of solar panels shall cease at 25mph (sustained wind), until wind subsides.

- Forecasted weather maximum temp (degrees F):
- Measured wind speed (MPH ground):
- Measured wind speed (MPH roof):

Heat Related Illness Prevention

- Employees shall have access to potable drinking water that is fresh, pure, and suitably cool. The water shall be located as close as practicable to the areas where employees are working. Water shall be supplied in sufficient quantity at the beginning of the work shift to provide at least one quart per employee per hour for drinking for the entire shift. Employees may begin the shift with smaller quantities of water if they identify the location and have effective means for replenishment during the shift to allow employees to drink one quart or more per hour. The frequent drinking of water shall be encouraged.
- Shade shall be present when temperature exceeds 80 degrees Fahrenheit. When the outdoor temperature in the work exceeds 80 degrees Fahrenheit, employees shall have and maintain one or more areas with shade at all times.
- New employees must be acclimatized. New employees will be monitored by their Crew Leader (site supervisor) for the first two (2) weeks of employment or longer when necessary.
- Employees will be allowed and encouraged to implement scheduled breaks during each shift. Employees must take cool-down breaks in the shade any time they feel the need to do so to protect them from overheating. Supervisors are REQUIRED to allow employees any break period they need during high heat conditions.
- Cool Vests are encouraged for all employees at all times during periods of high heat.
- Identify the location of the closest Occupational/Industrial Clinic or Hospital in case a crew member becomes ill.

What is the specific plan to provide and replenish sufficient water for all employees onsite?

- If offsite replenish is necessary, where will you go to replenish water (location/address):
- Who will replenish the drinking water (name):

Restroom Facilities

- Employees shall have access to restroom facilities with hand-washing stations. Use of onsite restroom is at the client's discretion (location is noted below). If client does not give permission, location of suitable restroom facilities with hand-washing stations at an offsite will be provided. The onsite supervisor will identify location and make arrangements to ensure all employees have access at any point.

- Restroom facilities will be (circle one): Onsite - Offsite
- If offsite, add location name and address:

Incident Reporting Procedure

- ✓ Contact your Site Supervisor
  - o Name:
  - o Phone:
- ✓ Contact your Manger
  - o Name:
  - o Phone:
- ✓ Contact the Incident Hotline
  - o (650) 963-5678 - Follow the voice prompts and provide us with:
    - Your full name, phone number, office location, brief description of what happened and when.

NOTE ADDITIONAL HAZARDS NOT ADDRESSED ABOVE  
(add as many as necessray by using additional sheets):

Define the hazard:	Method/steps to prevent incident:
Define the hazard:	Method/steps to prevent incident:


	JOB NUMBER:	JB-8042552 00	CUSTOMER:	Kevin Daly 35040 Country Green Ln Steamboat Springs, CO 80487	DESCRIPTION:	13.752 KW PV ARRAY	DESIGN:		
	MOUNTING SYSTEM:	TESLA SOLAR ROOF							
	MODULES:	(191) TESLA SR72T2; 72 W, 65.40 W PTC							
	INVERTER:	Multiple Inverters							
		303-808-5445	PAGE NAME:	JHA SHEET	SHEET:	SC 4	REV:	DATE:	4/26/2022

PARTIAL TILE LOCATIONS NEAR EDGE CONDITIONS ARE ESTIMATED.  
PLEASE VERIFY ACTUAL LENGTHS NEEDED ON SITE.

MP1	PITCH: 45° (12:12) ARRAY PITCH: 45° (12:12)		
	AZIMUTH: 174		ARRAY AZIMUTH: 174
	MATERIAL: Solar Roof		STORY: Two

Record Set Stamp

05/10/2022



MP1			
SYMBOL	PART	WIDTH (INCHES)	QUANTITY
	MONOLITH PV	45 1/8	191
	SINGLE	45 1/8	69
	5/6	37 5/8	29
	2/3	30 1/16	11
	1/2	22 9/16	19
	1/3	15 1/16	23
	1/6	7 1/2	10
	ROOF RACK	N/A	22


	JOB NUMBER: JB-8042552 00	CUSTOMER: Kevin Daly 35040 Country Green Ln Steamboat Springs, CO 80487  303-808-5445	DESCRIPTION: 13.752 KW PV ARRAY  PAGE NAME: MP1 TILE PLAN	DESIGN:   SHEET: SC 5 REV: 4/26/2022 DATE:	
	MOUNTING SYSTEM: TESLA SOLAR ROOF				
	MODULES: (191) TESLA SR72T2; 72 W, 65.40 W PTC				
	INVERTER: Multiple Inverters				

PARTIAL TILE LOCATIONS NEAR EDGE CONDITIONS ARE ESTIMATED.  
PLEASE VERIFY ACTUAL LENGTHS NEEDED ON SITE.

MP2	PITCH: 45° (12:12) ARRAY PITCH: 45° (12:12)	
	AZIMUTH: 354	ARRAY AZIMUTH: 354
	MATERIAL: Solar Roof	STORY: Two

Record Set Stamp

05/10/2022



MP2			
SYMBOL	PART	WIDTH (INCHES)	QUANTITY
<div></div>	MONOLITH PV	45 1/8	0
<div>6</div>	SINGLE	45 1/8	203
<div>5</div>	5/6	37 5/8	22
<div>4</div>	2/3	30 1/16	2
<div>3</div>	1/2	22 9/16	2
<div>2</div>	1/3	15 1/16	20
<div>1</div>	1/6	7 1/2	2
<div>R</div>	ROOF RACK	N/A	17

	JOB NUMBER: JB-8042552 00	CUSTOMER: Kevin Daly 35040 Country Green Ln Steamboat Springs, CO 80487  303-808-5445	DESCRIPTION: 13.752 KW PV ARRAY  PAGE NAME: MP2 TILE PLAN	DESIGN:   SHEET: SC 6 REV: DATE: 4/26/2022	
	MOUNTING SYSTEM: TESLA SOLAR ROOF				
	MODULES: (191) TESLA SR72T2; 72 W, 65.40 W PTC				
	INVERTER: Multiple Inverters				

PARTIAL TILE LOCATIONS NEAR EDGE CONDITIONS ARE ESTIMATED.  
PLEASE VERIFY ACTUAL LENGTHS NEEDED ON SITE.


MP3

PITCH: 45° (12:12) ARRAY PITCH: 45° (12:12)  
AZIMUTH: 354      ARRAY AZIMUTH: 354  
MATERIAL: Solar Roof

STORY: Two

Record Set Stamp

05/10/2022




MP3			
SYMBOL	PART	WIDTH (INCHES)	QUANTITY
	MONOLITH PV	45 1/8	0
6	SINGLE	45 1/8	119
5	5/6	37 5/8	16
4	2/3	30 1/16	1
3	1/2	22 9/16	0
2	1/3	15 1/16	16
1	1/6	7 1/2	0
R	ROOF RACK	N/A	10



Record Set Stamp

05/10/2022



MP4			
SYMBOL	PART	WIDTH (INCHES)	QUANTITY
	MONOLITH PV	45 1/8	0
	SINGLE	45 1/8	7
	5/6	37 5/8	4
	2/3	30 1/16	1
	1/2	22 9/16	0
	1/3	15 1/16	3
	1/6	7 1/2	1
	ROOF RACK	N/A	1




PARTIAL TILE LOCATIONS NEAR EDGE CONDITIONS ARE ESTIMATED.  
PLEASE VERIFY ACTUAL LENGTHS NEEDED ON SITE.

MP5

PITCH: 45° (12:12) ARRAY PITCH: 45° (12:12)  
AZIMUTH: 84      ARRAY AZIMUTH: 84  
MATERIAL: Solar Roof      STORY: Two


Record Set Stamp  
05/10/2022



MP5			
SYMBOL	PART	WIDTH (INCHES)	QUANTITY
<div></div>	MONOLITH PV	45 1/8	0
<div>6</div>	SINGLE	45 1/8	7
<div>5</div>	5/6	37 5/8	4
<div>4</div>	2/3	30 1/16	1
<div>3</div>	1/2	22 9/16	0
<div>2</div>	1/3	15 1/16	3
<div>1</div>	1/6	7 1/2	1
<div>R</div>	ROOF RACK	N/A	1

Record Set Stamp

05/10/2022




MP6			
SYMBOL	PART	WIDTH (INCHES)	QUANTITY
	MONOLITH PV	45 1/8	0
	SINGLE	45 1/8	7
	5/6	37 5/8	4
	2/3	30 1/16	1
	1/2	22 9/16	0
	1/3	15 1/16	3
	1/6	7 1/2	1
	ROOF RACK	N/A	1

PARTIAL TILE LOCATIONS NEAR EDGE CONDITIONS ARE ESTIMATED.  
PLEASE VERIFY ACTUAL LENGTHS NEEDED ON SITE.

MP7


PITCH: 45° (12:12) ARRAY PITCH: 45° (12:12)  
AZIMUTH: 84      ARRAY AZIMUTH: 84  
MATERIAL: Solar Roof      STORY: Two









Record Set Stamp  
05/10/2022



MP7			
SYMBOL	PART	WIDTH (INCHES)	QUANTITY
	MONOLITH PV	45 1/8	0
	SINGLE	45 1/8	7
	5/6	37 5/8	4
	2/3	30 1/16	1
	1/2	22 9/16	0
	1/3	15 1/16	3
	1/6	7 1/2	1
	ROOF RACK	N/A	1

MP8	PITCH: 45° (12:12) ARRAY PITCH: 45° (12:12) AZIMUTH: 264      ARRAY AZIMUTH: 264 MATERIAL: Solar Roof	STORY: Two  Record Set Stamp  05/10/2022
-----	---	--












MP8			
SYMBOL	PART	WIDTH (INCHES)	QUANTITY
	MONOLITH PV	45 1/8	0
	SINGLE	45 1/8	1
	5/6	37 5/8	3
	2/3	30 1/16	0
	1/2	22 9/16	1
	1/3	15 1/16	2
	1/6	7 1/2	2
	ROOF RACK	N/A	1

JOB NUMBER: JB-8042552 00 MOUNTING SYSTEM: TESLA SOLAR ROOF MODULES: (191) TESLA SR72T2; 72 W, 65.40 W PTC INVERTER: Multiple Inverters	CUSTOMER:	DESCRIPTION:	DESIGN:
	Kevin Daly	13.752 KW PV ARRAY	
	35040 Country Green Ln		
	Steamboat Springs, CO 80487		
	303-808-5445	PAGE NAME:	SHEET: REV: DATE:
		MP8 TILE PLAN	SC 12 4/26/2022

MP9	PITCH: 45° (12:12) ARRAY PITCH: 45° (12:12) AZIMUTH: 84 ARRAY AZIMUTH: 84 MATERIAL: Solar Roof STORY: Two
-----	---

05/10/2022



MP9			
SYMBOL	PART	WIDTH (INCHES)	QUANTITY
	MONOLITH PV	45 1/8	0
	SINGLE	45 1/8	1
	5/6	37 5/8	3
	2/3	30 1/16	0
	1/2	22 9/16	1
	1/3	15 1/16	2
	1/6	7 1/2	2
	ROOF RACK	N/A	1

JOB NUMBER: JB-8042552 00	CUSTOMER: Kevin Daly 35040 Country Green Ln Steamboat Springs, CO 80487	DESCRIPTION: 13.752 KW PV ARRAY	DESIGN:
MOUNTING SYSTEM: TESLA SOLAR ROOF			
MODULES: (191) TESLA SR72T2; 72 W, 65.40 W PTC			
INVERTER: Multiple Inverters	303-808-5445	PAGE NAME: MP9 TILE PLAN	SHEET: SC 13 REV: 4/26/2022 DATE:

PARTIAL TILE LOCATIONS NEAR EDGE CONDITIONS ARE ESTIMATED.  
PLEASE VERIFY ACTUAL LENGTHS NEEDED ON SITE.

6

5

4

3

2

1

R

MONOLITH PV

SINGLE

5/6

2/3

1/2

1/3

1/6

ROOF RACK

45 1/8

45 1/8

37 5/8

30 1/16

22 9/16

15 1/16

7 1/2

N/A

0

0

0

0

0

0

2

0

MP10

PITCH: 29° (7:12)    ARRAY PITCH: 29° (7:12)  
AZIMUTH: 213    ARRAY AZIMUTH: 213  
MATERIAL: Solar Roof    STORY: Two

Record Set Stamp  
05/10/2022

JOB NUMBER: JB-8042552 00

MOUNTING SYSTEM: TESLA SOLAR ROOF

MODULES: (191) TESLA SR72T2; 72 W, 65.40 W PTC

INVERTER: Multiple Inverters

CUSTOMER: Kevin Daly  
35040 Country Green Ln  
Steamboat Springs, CO 80487  
303-808-5445

DESCRIPTION: 13.752 KW PV ARRAY


PAGE NAME: MP10 TILE PLAN









DESIGN:

SHEET: SC 14    REV:    DATE: 4/26/2022

MP11	PITCH: 23° (5:12)    ARRAY PITCH: 23° (5:12) AZIMUTH: 174    ARRAY AZIMUTH: 174 MATERIAL: Solar Roof    STORY: Two
------	--

05/10/2022



MP11			
SYMBOL	PART	WIDTH (INCHES)	QUANTITY
	MONOLITH PV	45 1/8	0
	SINGLE	45 1/8	1
	5/6	37 5/8	2
	2/3	30 1/16	2
	1/2	22 9/16	0
	1/3	15 1/16	1
	1/6	7 1/2	1
	ROOF RACK	N/A	1

	JOB NUMBER: JB-8042552 00	CUSTOMER:	DESCRIPTION:	DESIGN:	
	MOUNTING SYSTEM:	Kevin Daly	13.752 KW PV ARRAY		
	TESLA SOLAR ROOF	35040 Country Green Ln			
	MODULES:	Steamboat Springs, CO 80487			
	(191) TESLA SR72T2; 72 W, 65.40 W PTC		PAGE NAME:	SHEET: REV: DATE:	
	INVERTER:	303-808-5445	MP11 TILE PLAN	SC 15 4/26/2022	
	Multiple Inverters				



PARTIAL TILE LOCATIONS NEAR EDGE CONDITIONS ARE ESTIMATED.  
PLEASE VERIFY ACTUAL LENGTHS NEEDED ON SITE.

6

5

4

3

2

1

R

MONOLITH PV

SINGLE

5/6

2/3

1/2

1/3

1/6

ROOF RACK

45 1/8

45 1/8

37 5/8

30 1/16

22 9/16

15 1/16

7 1/2

N/A

0

0

0

0

0

0

2

0

MP12

SYMBOL

PART

WIDTH (INCHES)

QUANTITY

MP12

PITCH: 29° (7:12)    ARRAY PITCH: 29° (7:12)

AZIMUTH: 136    ARRAY AZIMUTH: 136

MATERIAL: Solar Roof    STORY: Two

Record Set Stamp

05/10/2022

JOB NUMBER: JB-8042552 00

MOUNTING SYSTEM: TESLA SOLAR ROOF

MODULES: (191) TESLA SR72T2; 72 W, 65.40 W PTC

INVERTER: Multiple Inverters


CUSTOMER: Kevin Daly  
35040 Country Green Ln  
Steamboat Springs, CO 80487  
303-808-5445

DESCRIPTION: 13.752 KW PV ARRAY

PAGE NAME: MP12 TILE PLAN

DESIGN:

SHEET: SC 16    REV:    DATE: 4/26/2022



MP1	PITCH: 45° (12:12) ARRAY PITCH: 45° (12:12)	
	AZIMUTH: 174	ARRAY AZIMUTH: 174
	MATERIAL: Solar Roof	
		STORY: Two
		Record Set Stamp
		05/10/2022

	JOB NUMBER:	JB-8042552 00	CUSTOMER:	Kevin Daly	DESCRIPTION:	13.752 KW PV ARRAY	DESIGN:	
	MOUNTING SYSTEM:	TESLA SOLAR ROOF		35040 Country Green Ln				
	MODULES:	(191) TESLA SR72T2; 72 W, 65.40 W PTC		Steamboat Springs, CO 80487				
	INVERTER:	Multiple Inverters		303-808-5445				
				PAGE NAME:	STRING DIAGRAM	SHEET:	REV:	DATE:
						SC 17		4/26/2022





PHOTOVOLTAIC POWER SOURCE

Label Location:  
(C)  
Per Code:  
NEC 690.31.E.3

DC PHOTOVOLTAIC  
DISCONNECT

Label Location:  
(DC) (INV)  
Per Code:  
NEC 690.14.C.2

MAXIMUM VOLTAGE   
MAXIMUM CIRCUIT CURRENT   
MAX RATED OUTPUT CURRENT  
OF THE CHARGE CONTROLLER   
OR DC-TO-DC CONVERTER  
(IF INSTALLED)

Label Location:  
(DC) (INV)  
Per Code:  
NEC 690.53

AC PHOTOVOLTAIC  
DISCONNECT

Label Location:  
(AC) (POI)  
Per Code:  
NEC 690.14.C.2

MAXIMUM AC  A  
OPERATING CURRENT  
MAXIMUM AC  V  
OPERATING VOLTAGE

Label Location:  
(AC) (POI)  
Per Code:  
NEC 690.54

WARNING

ELECTRIC SHOCK HAZARD  
DO NOT TOUCH TERMINALS  
TERMINALS ON BOTH LINE AND  
LOAD SIDES MAY BE ENERGIZED  
IN THE OPEN POSITION

Label Location:  
(AC) (POI)  
Per Code:  
CEC 690.13.B

CAUTION

DUAL POWER SOURCE  
SECOND SOURCE IS  
PHOTOVOLTAIC SYSTEM

Label Location:  
(POI)  
Per Code:  
NEC 705.12.B.3

WARNING

INVERTER OUTPUT  
CONNECTION  
DO NOT RELOCATE  
THIS OVERCURRENT  
DEVICE

Label Location:  
(POI)  
Per Code:  
NEC 705.12.B.2.3.b

WARNING

THIS EQUIPMENT FED BY  
MULTIPLE SOURCES. TOTAL  
RATING OF ALL OVER CURRENT  
DEVICES, EXCLUDING MAIN  
SUPPLY OVERCURRENT DEVICE,  
SHALL NOT EXCEED AMPACITY  
OF BUSBAR.

Per Code:  
705.12.B.2.3.c

WARNING

ELECTRIC SHOCK HAZARD  
THE DC CONDUCTORS OF THIS  
PHOTOVOLTAIC SYSTEM ARE  
UNGROUNDDED AND  
MAY BE ENERGIZED

Label Location:  
(DC) (INV)

Record Set Stamp

05/10/2022

(AC): AC Disconnect  
(C): Conduit  
(CB): Combiner Box  
(D): Distribution Panel  
(DC): DC Disconnect  
(IC): Interior Run Conduit  
(INV): Inverter With Integrated DC Disconnect  
(LC): Load Center  
(M): Utility Meter  
(POI): Point of Interconnection

Label Set